

DELAWARE RIVER AND BAY AUTHORITY

DELAWARE AIRPARK

ADDENDUM NO. 1

TO

CONTRACT NO. 33N-24-A

CONSTRUCT BOX HANGAR

November 14, 2023

To all concerned:

The original Contract Documents issued on November 1, 2023, shall be amended as noted herein. This Addendum No. 1 shall hereby become part of the Contract Documents. **Bidders must acknowledge this Addendum in the space provided on the signature page of the Bid forms.**

Amendment No. 1: Written Questions/Answers (see below).

* * * * *

CONTRACT NO. 33N-24-A
Addendum No. 1; Amendment No. 1

Questions/Answers

- Q1. Specification 133419, Section 2.4; A1, states roof paint finish two-coat fluoropolymer (siliconized polyester). There are two different coatings of fluoropolymer. What is the coating that needs to be provided?
- A1. The Contractor is to provide galvalume finish for roof panels.
- Q2. Specification 133419, Section 2.7; E. Gutters. The Plans do not show this condition. Will gutters be required for this project? If yes, what type of gutters will be needed? What is the intent for gutters & D.S.?
- A2. Gutters and downspouts are not to be provided.
- Q3. There are no specifications for exterior wall panels in terms of gauge thickness and coating. Can these specifications be provided?
- A3. Exterior wall panels are to be 26-gauge panels with a factory finish rust-inhibitive weather-resistant backend enamel of 1 mil minimum thickness. The color is to be selected from the manufacturer's full range.

- Q4. There are no specifications for interior partition wall materials in terms of gauge thickness and finish, one side or both sides of interior columns. Can these specifications be provided?
- A4. The Contractor is to provide 28-gauge metal panels with galvalume finish for interior partition panels, one side of the interior columns per detail shown on the Plans.