



## ADDENDUM

# 02 | 240305

---

**Delaware County Intermediate Unit**

Construction of the Morton Annex Addition and Site Repairs

**Date of Addendum:** March 05, 2024

**Marotta/Main Architects Project No.**  
22-DCIU-02

The original Project Manuals and Drawings dated 19 February, 2024 for the project noted above, are amended as noted in this Addendum No. 02.

Receipt of this Addendum shall be acknowledged by inserting its number and date in the space provided on the Bid Form.

This Addendum consists of 02 Pages and all attachments listed.

## CLARIFICATIONS

- 02.01 Basis of design Insulated metal wall panel Kingspan Shadowline:
- Specified gauges are for both side of the panel.
  - Panel Width: 24"
  - Finish:
    - o Non-embossed both sides.
    - o Exterior: Two coat fluoropolymer.
    - o Interior: "Imperial White" siliconized modified polyester finish.

## VOLUME 1 - LEGAL SPECIFICATIONS

- 02.02 Refer to Specification section 01 21 00 REVISE 3.3 B to read as follows:
- B. ELECTRICAL: To be included in the Electrical Construction Contract Base Bid Only
1. Material Allowance 26A –Additional 20 AMP Duplex Receptacles:
    - a. Description: In addition to the work shown on the drawings and specifications, provide and install a total of ten (10) additional duplex receptacle outlets each including outlet box, wall plate, 100' of concealed wire (2-#12 and 1-#12 ground) in a ¾" EMT conduit and connection to spare branch circuit protective device in a panel board in accordance with Unit Price 26A.
  2. Material Allowance 27A – Tele/Data Drops:
    - a. Description: In addition to the work shown on the drawings and specifications, provide and install ten (10) additional tele/data outlets, including outlet box, plate with double jack, 25' of ¾" EMT conduit, 200' of Cat 6 data cable, terminations at both work station and patch panel at nearest IDF or MDF room and testing in accordance with Unit Price 27A.
  3. Material Allowance 28A – Fire Alarm Audible/Visual Device:

- a. Description: In addition to the work shown on the drawings and specifications, provide and install a total of three (3) additional fire alarm A/V device assemblies, consisting of A/V device, backbox, up to 50 linear feet of ¾" EMT conduit, cabling and all terminations and connections to fire alarm system and programming required in accordance with Unit Price 28A.
- 4. Material Allowance 28B – Smoke Detector.
  - a. Description: In addition to the work shown on the drawings and specifications, provide and install a total of three (3) additional fire alarm initiating devices which will include the following: one smoke detector unit and backbox as specified; 50 linear feet of ¾" EMT conduit, cabling, terminations and connections to the fire alarm system and programming required in accordance with Unit Price 28C.

**END OF ADDENDUM 02**

Respectfully Submitted,

Wayne Manley, Project Manager  
Marotta/Main Architects, Inc.

**Attachments:**