

AGCS STATE ROAD ADMINISTRATION

110 E State Rd, West Grove, PA 19390

11-09-2026: BID ISSUE

CLIENT
Avon Grove Charter School
110 E State Rd
West Grove, PA 19390
484-667-5000

ARCHITECTURAL
Heckendorn Shiles Architects
347 East Conestoga Road
Wayne, PA 19087
610-994-3500

STRUCTURAL
Orndorf & Associates, Inc
8600 West Chester Pike, Suite 201
Upper Darby, PA 19802

MEPFP
Schiller & Hersh Associates, Inc.
636 Skippack Pike, Suite 200
Blue Bell, PA 19422
215-886-8947

11/10/2026 3:58:40 PM HECKENDORN SHILES ARCHITECTS expressly reserves its common law copyright and other property rights in these plans. These are not to be reproduced, nor are they to be assigned to any third party, without first obtaining the expressed written consent of HECKENDORN SHILES ARCHITECTS

POWER AND COMM. LEGEND

OUTLETS

- WALL MTD. DUPLEX RECEPTACLE OUTLET
- WALL MTD. DUPLEX RECEPTACLE OUTLET GFI = GROUND FAULT INTERRUPTER
- WALL MTD. DUPLEX RECEPTACLE OUTLET W/ UNINTERRUPTED POWER SOURCE
- WALL MTD. QUADRUPLEX RECEPTACLE
- WALL MTD. QUADRUPLEX RECEPTACLE OUTLET GFI = GROUND FAULT INTERRUPTER
- WALL MTD. DEDICATED DUPLEX RECEPTACLE OUTLET
- WALL MTD. TEL. OUTLET
- WALL MTD. DATA OUTLET
- WALL MTD. COMBINATION TELEPHONE AND DATA OUTLET
- 2 DATA / 2 PHONE JACKS (WALL MOUNTED OR BASE FEED)
- JUNCTION BOX

ALTERNATE SYMBOLS SELECTION:
COORDINATE WITH PROJECT MEP ENGINEER'S SYMBOLS

- COMBINATION POWER, TELEPHONE AND DATA FLOOR OUTLET (FLUSH MOUNTED)
- THRU-WALL POWER/COMMUNICATIONS INFEED
- TELEVISION OUTLET

FIRE ALARM AND SAFETY

- FA — FIRE ALARM SPEAKER
- S — PA SPEAKER
- FW — FIRE WARDEN STATION
- H/S — COMBINATION HORN & STROBE
- MF — MANUAL FIRE ALARM PULL STATION (SEE MTG. HEIGHT SCHEDULE)
- S — WALL MOUNTED STROBE
- FEC — FEC (FIRE EXTINGUISHER CABINET)
- FE — FE (FIRE EXTINGUISHER - WALL MOUNTED)

SWITCHES

- MD — MOTION DETECTOR

ELECTRONIC HARDWARE

- H — HOLD OPEN
- ML — MAGNETIC LOCK (SEE HARDWARE SCHEDULE)
- EL — ELECTRIC LOCKSET (SEE HARDWARE SCHEDULE)
- ES — ELECTRIC STRIKE (SEE HARDWARE SCHEDULE)
- DC — DOOR CONTACTS
- CR — CARD READER

SIGNAL SYSTEMS

- STATIONARY SECURITY CAMERA
- PT — ZOOM, PAN, TILT SECURITY CAMERA
- 2 — EQUIPMENT ITEM - SEE SCHEDULE

CEILING LEGEND

- 0'-0" / ABC.1 — CEILING HEIGHT / CEILING TYPE
- SUSPENSION GRID & 2' X 2' LAY-IN ACOUSTIC CEILING TILE
- SUSPENSION GRID & 2' X 4' LAY-IN ACOUSTIC CEILING TILE
- GWB SOFFIT OR CEILING
- 2X2 SURFACE LIGHT FIXTURE
- 2X4 SURFACE LIGHT FIXTURE
- 1X4 SURFACE LIGHT FIXTURE
- 4' SURFACE MOUNT LINEAR LIGHT FIXTURE
- SURFACE MOUNTED
- RECESSED DOWNLIGHT
- 2X2 RECESSED LIGHT FIXTURE
- 2X4 RECESSED LIGHT FIXTURE
- 1X4 RECESSED LIGHT FIXTURE
- TRACK LIGHTING FIXTURE
- WALL SCONCE
- PENDANT MOUNTED LINEAR
- E — WALL MOUNTED EMERGENCY LIGHTING
- SUPPLY AIR DIFFUSER
- DIRECTIONAL SUPPLY AIR DIFFUSER
- LINEAR SLOT DIFFUSER
- RETURN AIR DIFFUSER
- SPRINKLER HEAD
- EXIT SIGN - WALL MOUNTED ILLUMINATED SINGLE & DOUBLE FACE DIRECTIONAL ARROWS AS INDICATED
- EXIT SIGN - CEILING MOUNTED ILLUMINATED SINGLE & DOUBLE FACE DIRECTIONAL ARROWS AS INDICATED
- SD — CEILING MOUNTED SMOKE DETECTOR
- FA — FIRE ALARM SPEAKERS
- S — PA SPEAKER
- WP — START OF CONSTRUCTION/CEILING WORK POINT

ARCHITECTURAL LEGEND

- ROOM NAME / 101 — ROOM IDENTIFICATION
- 101B — DOOR IDENTIFICATION
- 1 / AXXX — ENLARGED PLAN OR DETAIL MARK
- 1 / XXX / 1 — MULTIPLE ELEVATION REFERENCE
- 1 / AXXX — ELEVATION REFERENCE
- 1 / AXXX / SIM — SECTION REFERENCE
- WP — WORKING POINT OR DATUM
- XXXX — PARTITION TYPE
- XX — COLUMN GRID
- PLAN NORTH — NORTH ARROW
- 100.5' — SPOT ELEVATION TAG
- P.1 — FINISH TAG
- XXX — EQUIPMENT TAG
- FINISH FLOOR ELEVATION TAG
- 1 — WINDOW TAG
- EXISTING CONSTRUCTION
- DEMOLISH; REMOVE CONSTRUCTION
- NEW CONSTRUCTION
- BUILT-IN CASEWORK
- SOFFIT, OPEN ABOVE
- REMOVE DOOR, FRAME, & HARDWARE

MATERIALS LEGEND (VIEWED IN SECTION)

- EARTH, UNDISTURBED
- EARTH, COMPACTED FILL
- CRUSHED ROCK GRAVEL
- CONCRETE, CAST STONE (SECTION OR ELEVATION)
- CONCRETE MASONRY
- BRICK
- RIGID INSULATION
- PLASTER OR GYPSUM BOARD (SECTION OR ELEVATION)
- SOLID WOOD (SECTION OR ELEVATION)
- PLYWOOD
- PARTICLE BOARD
- SOLID SURFACE
- STONE (MARBLE/GRANITE)
- WOOD BLOCKING OR SHIM
- WOOD FRAMING, CONTINUOUS
- STEEL

DEMOLITION GENERAL NOTES

1. THESE DRAWINGS ARE MEANT TO OUTLINE GENERAL SCOPE OF DEMOLITION FOR THE CONTRACTOR. THE SPECIFIC AREAS, ITEMS, DETAILS, MATERIALS, ETC. OF DEMOLITION WILL BE A RESULT OF FIELD CONDITIONS. THE INTENT IS THAT ALL DEMOLITION REQUIRED TO PROPERLY CONSTRUCT THIS PROJECT IS THE RESPONSIBILITY OF THE PRIME CONTRACTOR. THE CONTRACTOR WILL INSURE THAT THE EXIST. BUILDING RETAINS STRUCTURAL INTEGRITY AND REMAINS WATER AND WEATHER-TIGHT DURING THE DEMOLITION AND CONSTRUCTION PHASES OF THE WORK.
2. CONTRACTOR MUST REVIEW NEW WORK INDICATED IN 'A' SERIES DRAWINGS AND COORDINATE DEMOLITION WORK WITH NEW WORK.
3. CONTRACTOR MUST COORDINATE ALL ARCHITECTURAL DEMOLITION WITH MECHANICAL/ELECTRICAL/PLUMBING DEMOLITION WORK AS SHOWN ON 'M', 'P, 'E' SERIES DRAWINGS. THE PRIME CONTRACTORS WILL BE RESPONSIBLE FOR THE CONTINUOUS INTERNAL UTILITIES DISTRIBUTION INCLUDING BUT NOT LIMITED TO THE WATER & ELECTRICAL DISTRIBUTION SYSTEMS.
4. CONTRACTOR MUST COORDINATE ALL ARCHITECTURAL DEMOLITION WITH STRUCTURAL DEMOLITION WORK AS SHOWN ON 'S' SERIES DRAWINGS.
5. CONTRACTOR MUST COORDINATE COURSE OF DEMOLITION WORK WITH OVERALL CONSTRUCTION SCHEDULE.
6. CAREFULLY COORDINATE ALL DEMOLITION WORK WITH EXIST. CONSTRUCTION TO REMAIN. ANY EXIST. CONSTRUCTION TO REMAIN THAT IS DAMAGED BY DEMOLITION SHALL BE REPAIRED/REPLACED TO MATCH ORIGINAL CONDITION. SEE SPECIFICATIONS FOR CLARIFICATION OF RESPONSIBILITY.
7. GENERAL CONTRACTOR IS RESPONSIBLE TO PATCH/REPAIR ALL FINISH SURFACES AFFECTED BY DEMOLITION WORK. SEE THE GENERAL REQUIREMENTS SECTIONS OF THE SPECIFICATION.
8. GENERAL CONTRACTOR SHALL COORDINATE, PRIOR TO ANY DEMOLITION, WHAT MATERIALS OR ITEMS OF EQUIPMENT ARE TO BE RETAINED BY THE OWNER. ALL OTHER DISMANTLED MATERIALS SHALL BECOME THE PROPERTY OF THE CONTRACTOR AND SHALL BE REMOVED FROM THE PREMISES ACCORDING TO ALL APPLICABLE CODES.
9. CARE SHOULD BE TAKEN TO AVOID DISTURBING ANY SYSTEM LINES WHICH ARE TO REMAIN. PRIOR TO THE START OF CONSTRUCTION, GENERAL CONTRACTOR MUST COORDINATE W/ ELECTRICAL CONTRACTOR WHICH LINES ARE TO REMAIN IN SERVICE.
10. GENERAL CONTRACTOR MUST CAREFULLY COORDINATE DEMOLITION OF EXTERIOR WALLS WITH THE INTENT OF THE NEW CONSTRUCTION. ALL FOOTINGS AND STRUCTURAL MEMBERS SHALL REMAIN INTACT, UNLESS NOTED OTHERWISE. CONTRACTOR TO COORDINATE W/ STRUCTURAL DWGS.
11. REFER TO SPECIFICATIONS FOR ADDITIONAL INFORMATION.
12. THE GENERAL CONTRACTOR IS RESPONSIBLE FOR ALL TEMPORARY SHORING AND BRACING OF STRUCTURE PRIOR TO AND DURING DEMOLITION AND NEW CONSTRUCTION.
13. WHERE WALLS ARE INDICATED TO BE REMOVED, CONTRACTOR MUST FIELD VERIFY IF THE WALLS ARE STRUCTURAL BEARING WALLS. IF IT IS DETERMINED THAT THE WALLS TO BE REMOVED ARE BEARING, THE CONTRACTOR IS RESPONSIBLE TO PROVIDE TEMPORARY SUPPORT AT AREAS WHERE WALLS ARE TO BE REMOVED. IF THE CONTRACTOR CANNOT DETERMINE IF THE WALL IS BEARING, THE CONTRACTOR MUST CONTACT THE PROJECT STRUCTURAL ENGINEER FOR CLARIFICATION PRIOR TO COMMENCING WORK.

CONSTRUCTION GENERAL NOTES

1. ALL DRAWINGS ARE TO BE USED IN CONJUNCTION WITH SPECIFICATIONS IN DETERMINING THE FULL PROJECT SCOPE.
2. REFER TO MEP DWGS FOR MECHANICAL, ELECTRICAL, PLUMBING WORK.
3. REFER TO STRUCTURAL DWGS FOR STRUCTURAL WORK.
4. DO NOT SCALE DRAWINGS: WRITTEN DIMENSIONS GOVERN PARTITION LOCATIONS, DIMENSIONS AND TYPES. IN CASE OF CONFLICT, NOTIFY ARCHITECT FOR WRITTEN CLARIFICATIONS PRIOR TO PROCEEDING W/ CONSTRUCTION. CONSTRUCTION PLAN BY ARCHITECT SUPERCEDES OTHER PLANS.
5. DIMENSIONS MARKED "CLEAR" OR "CLR" SHALL BE MAINTAINED AND SHALL ALLOW FOR THICKNESS OF FINISHES INCLUDING CARPET, VCT, ETC. CONTRACTOR SHALL NOT ADJUST DIMENSIONS WITHOUT WRITTEN INSTRUCTIONS FROM THE ARCHITECT.
6. DIMENSIONS SHOWN AS "VIF" SHALL BE VERIFIED BY THE CONTRACTOR IN THE FIELD BY LAYING OUT THE PARTITIONS. CONTRACTOR SHALL NOTIFY ARCHITECT OF ANY DISCREPANCY IN DIMENSIONS PRIOR TO PROCEEDING WITH THE WORK IN THE AREA.
7. PARTITION CONSTRUCTION SHALL COMMENCE ONLY AFTER THE ARCHITECT HAS REVIEWED LAYOUT.
8. CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND JOB CONDITIONS PRIOR TO STARTING WORK AND SHALL REPORT TO THE ARCHITECT ANY DISCREPANCIES OR OMISSIONS WHICH WOULD INTERFERE WITH SATISFACTORY COMPLETION OF WORK.
9. ALL BUILDING DEPARTMENT PERMITS SHALL BE OBTAINED PRIOR TO COMMENCEMENT OF WORK.
10. PROVIDE PORTABLE FIRE EXTINGUISHERS IN COMPLIANCE WITH INTERNATIONAL FIRE CODE SECTION 906
11. REFER TO SPECIFICATIONS FOR ADDITIONAL INFORMATION.
12. PENETRATIONS IN ROOF/ROOF MEMBRANE TO BE COMPLETED BY GC ONLY. GC TO COORDINATE ALL OF PENETRATIONS WITH OTHER PRIMES AND PROVIDE ROOF REPAIRS/ INSTALLATION AS REQUIRED. MC TO PROVIDE CURBS FOR INSTALLATION. GC TO PROVIDE PT WOOD BLOCKING AS REQUIRED FOR LEVEL INSTALLATION.
13. ALL WORK TO BE COMPLETED IN A MANNER TO ENSURE THE EXISTING ROOF WARRANTY IS MAINTAINED.
14. THE SCHOOL DATA VENDOR WILL BE ONSITE TO DEMOLISH AND REPLACE DATA CABLING DURING DEMOLITION AS REQUIRED GC TO COORDINATE TO PROVIDE ACCESS AND TO COORDINATE EFFORTS.
15. THE SCHOOL HAS BEEN MADE AWARE THAT THERE IS ASBESTOS CONTAINING MATERIAL ONSITE. IT IS LIKELY TO BE ENCOUNTERED AT THE EXTERIOR WINDOWS AND IN-WALL PIPE INSULATION. SCHOOL WILL TEST AND ANY ABATEMENT REQUIRED WILL BE ADDRESSED BY THE SCHOOL.

DRAWING LIST

REFER TO ENGINEERING COVER SHEETS FOR DRAWING LISTS

DRAWING LIST

NUMBER	SHEET NAME	11-09-2026 BID ISSUE
A000	COVER SHEET	X
A001	DRAWING LIST, LEGENDS, ABBREVIATIONS	X
A002	CODE ABSTRACT / INTERIOR SIGNAGE PLAN	X
A003	PHASING/ STAGING PLANS	X
A004	EXISTING PHOTOGRAPHS	X
A005	EXISTING PHOTOGRAPHS	X
AD101	EXISTING CONDITIONS & DEMOLITION - FIRST FLOOR PLAN	X
AD102	EXISTING CONDITIONS & DEMOLITION - ROOF PLAN	X
AD110	EXISTING CONDITIONS & DEMOLITION - FIRST FLOOR RCP	X
AD200	EXISTING CONDITIONS & DEMO - EXT. ELEVS AND SECTIONS	X
AD300	EXISTING CONDITIONS & DEMOLITION - BUILDING SECTIONS	X
A101	NEW CONSTRUCTION PLAN	X
A102	NEW CONSTRUCTION ROOF PLAN	X
A110	NEW CONSTRUCTION REFLECTED CEILING PLAN	X
A120	NEW CONSTRUCTION FINISH PLAN	X
A130	NEW CONSTRUCTION FFE PLAN	X
A200	NEW CONSTRUCTION EXTERIOR ELEVATIONS	X
A300	NEW CONSTRUCTION BUILDING SECTIONS	X
A310	NEW CONSTRUCTION WALL SECTIONS	X
A401	ENLARGED PLAN AND INT. ELEVATIONS - SECTOR B	X
A400	ENLARGED PLAN AND INT. ELEVATIONS - SECTOR A	X
A402	ENLARGED PLAN & EXTERIOR ELEVATIONS - CANOPY	X
A500	DETAILS - TRANSITIONS	X
A501	DETAILS - CASEWORK	X
A502	DETAILS - GREETER DESK AND MISC. DETAILS	X
A503	DETAILS - INTERIOR STOREFRONT, DOORS & COLUMN WRAP	X
A504	DETAILS - EXTERIOR WALL & WINDOW	X
A506	DETAILS - ROOF	X
A505	DETAILS - EXTERIOR WALL & SITE	X
A600	PARTITION SCHEDULE & DETAILS	X
A601	SCHEDULES	X


STRUCTURAL DRAWING LIST

NUMBER	SHEET NAME	11-09-2026 BID ISSUE
S0.0	STRUCTURAL NOTES	X
S1.0	STRUCTURAL PLANS	X
S5.0	STRUCTURAL DETAILS	X
S5.1	FRAMING DETAILS & SCHEDULES	X

ALTERNATES

ALTERNATE 1:
BASE SCOPE: CEILING GRID AND LIGHT FIXTURES IN CORRIDOR TO REMAIN. NEW ACOUSTIC CEILING TILE TO BE PROVIDED.
ALTERNATE SCOPE: CEILING GRID AND LIGHT FIXTURES IN CORRIDOR TO BE REMOVED AND NEW CEILING GRID, TILES AND LIGHTS TO BE PROVIDED.

ALTERNATE 2:
BASE SCOPE: NO BOLLARDS TO BE PROVIDED INSTALLED.
ALTERNATE SCOPE: PROVIDE BOLLARDS AS INDICATED ON PLAN IN EXISTING SIDEWALK.



AXONOMETRIC BUILDING KEY PLAN

AGCS STATE ROAD ADMINISTRATION

110 E State Rd, West Grove, PA 19390

HSA PROJECT # :26-004

[redacted] HSA
Heckendorn Shiles Architects

PROJECT TEAM

CLIENT
Avon Grove Charter School
110 E State Rd
West Grove, PA 19390
484-667-5000

ARCHITECTURAL
Heckendorn Shiles Architects
347 East Conestoga Road
Wayne, PA 19087
610-994-3500

STRUCTURAL
Orndorf & Associates, Inc
8600 West Chester Pike, Suite 201
Upper Darby, PA 19802

MEPFP
Schiller & Hersh Associates, Inc.
636 Skippack Pike, Suite 200
Blue Bell, PA 19422
215-886-8947

NOT FOR CONSTRUCTION

ISSUE HISTORY

Δ	DATE	ISSUED FOR
1	11-09-2026	BID ISSUE

SHEET TITLE
DRAWING LIST, LEGENDS, ABBREVIATIONS

DRAWING NUMBER
A001

11/10/2026 3:58:43 PM HECKENDORN SHILES ARCHITECTS expressly reserves its common law copyright and other property rights in these plans. These are not to be reproduced, nor are they to be assigned to any third party, without first obtaining the expressed written consent of HECKENDORN SHILES ARCHITECTS

Table 703.2.4—Visual Character Height

Height above Floor to Baseline of Character	Horizontal Viewing Distance	Minimum Character Height
40 inches (1015 mm) to less than or equal to 70 inches (1780 mm)	Less than 6 feet (1830 mm)	5/8 inch (16 mm)
	6 feet (1830 mm) and greater	5/8 inch (16 mm), plus 1/8 inch (3.2 mm) per foot (305 mm) of viewing distance above 6 feet (1830 mm)
Greater than 70 inches (1780 mm) to less than or equal to 120 inches (3050 mm)	Less than 15 feet (4570 mm)	2 inches (51 mm)
	15 feet (4570 mm) and greater	2 inches (51 mm), plus 1/8 inch (3.2 mm) per foot (305 mm) of viewing distance above 15 feet (4570 mm)
Greater than 120 inches (3050 mm)	Less than 21 feet (6400 mm)	3 inches (75 mm)
	21 feet (6400 mm) and greater	3 inches (76 mm), plus 1/8 inch (3.2 mm) per foot (305 mm) of viewing distance above 21 feet (6400 mm)

Table 703.4.3— Braille Dimensions

Measurement range	Minimum in inches Maximum in inches
Dot base diameter	0.059 (1.5 mm) to 0.063 (1.6 mm)
Distance between two dots in the same cell	0.090 (2.3 mm) to 0.100 (2.5 mm)
Distance between corresponding dots in adjacent cells[1]	0.241 (6.1 mm) to 0.300 (7.6 mm)
Dot height	0.025 (0.6 mm) to 0.037 (0.9 mm)
Distance between corresponding dots from one cell directly below[1]	0.395 (10.0 mm) to 0.400 (10.2 mm)

[1]Measured center to center




Fig. 703.4.3
Braille Measurement






Fig. 703.3.11
Location of Tactile Signs at Doors




Fig. 703.3.5
Character Height





Fig. 703.4.4
Position of Braille

7




*Note: For Braille mounting height see Section 703.4.5 (48" min to baseline of Braille cell).

Fig. 703.3.10
Height of Tactile Characters above Floor or Ground

INTERIOR ROOM SIGNAGE SCHEDULE		
SIGN TAG	SIGN LABEL	REMARKS
E1	EXIT	BOD: EVU1-82. ANTICIPATED SIGN SIZE 8-1/2" X 2-1/2"
A1	ADMIN	BOD: EVU1-82
R3	RESTROOM	PROVIDE UNISEX RESTROOM SIGNAGE SHOWING HANDICAP ACCESSIBILITY BOD: EVU1-R3. ANTICIPATED SIGN SIZE 8-1/2" X 8-9/16"
RS1		PROVIDE STANDARD ROOM SIGNAGE W/ REMOVABLE NAME SLOT, INCLUDE RM NAME AND SIGNAGE NUMBER BOD: EVU1-812
RS2		BOD: EVU1-82 OR B4, HEIGHT OF SIGN AS REQUIRED TO FIT TEXT AND BRAILLE

NOTES:
1. REFER TO FIXTURE/DEVICE MOUNTING HEIGHT SCHEDULE ON A603 FOR SIGNAGE MOUNTING HEIGHT INFO.
2. ALL SIGNAGE MUST COMPLY W/ ICC/ ANSI A117.1-2017
3. ALL SIGNAGE MUST COMPLY W/ LIMITS OF PROTRUDING OBJECTS.
4. VISUAL CHARACTERS MUST COMPLY W/ ICC/ ANSI A117.1-2017 SECTION 703.2.
5. ALL SIGNAGE MUST BE TACTILE AND MUST COMPLY W/ ICC/ ANSI A117.1-2017 SECTIONS 703.5
6. SYMBOLS & PICTOGRAMS MUST COMPLY W/ ICC/ ANSI A117.1-2017 703.5 & 703.6
7. TYPICAL SIGN REQUIREMENTS (U.N.O)
   A. SIGN SIZE; AS RECOMMENDED BY MFGR AND AS REQUIRED BY CODE U.N.O.
   B. MESSAGE PANEL MATERIAL; MFGR STANDARD.
   C. MESSAGE PANEL FINISH/COLOR; AS SELECTED BY ARCHITECT FROM MANUFACTURER'S FULL RANGE.
   D. BACKGROUND FINISH/ COLOR; AS SELECTED BY ARCHITECT FROM MANUFACTURERS FULL RANGE.
   E. CHARACTER SIZE; 3/8" TYPEFACE, ACCOMPANIED BY GRADE 2 BRAILLE U.N.O.
   F. CHARACTER FINISH/ COLOR; AS SELECTED BY ARCHITECT FROM MANUFACTURERS FULL RANGE.
8. SIGNAGE MOUNTED ON GLASS. PROVIDE BLANK PANEL ADHERED TO OPPOSITE FACE OF GLASS
9. ROOM NAMES AND NUMBERS TO BE CONFIRMED WITH OWENR PRIOR TO MANUFACTURING
10. MOUNTING LOCATIONS TO BE REVIEWED IN FIELD WITH OWNER/ARCHITECT PRIOR TO INSTALLATION.
11. SIGNS TO BE 8.5" WIDE TYPICALLY, U.N.O. SIGN HEIGHT DEPENDANT ON ROOM TYPE. REFER TO REDMARKS AND SPECIFICATION FOR ADDITIONAL INFORMATION
12. BASIS OF DESIGN SIGNAGE MANUFACTURER : APCO. REFER TO SPECIFICATION FOR ADDITIONAL INFORMATION.
13. ALL SIGNAGE TO INCLUDE ROOM NUMBER/FIRE REFERENCE NUMBER. SEE SIGNAGE PLAN FOR RELEVANT NUMBER INFORMATION. SEE ELEVATION ON THIS SHEET FOR NUMBER LOCATION ON SIGNAGE.

2 A002 TACTILE SIGNAGE
1/2" = 1'-0"



1 A002 SIGNAGE PLAN
3/16" = 1'-0"

HEICKENDORN SHILES ARCHITECTS expressly reserves its common law copyright and other property rights in these plans. These are not to be reproduced, nor are they to be assigned to any third party, without first obtaining the expressed written consent of HEICKENDORN SHILES ARCHITECTS

11/10/2026 3:58:44 PM

AGCS STATE ROAD ADMINISTRATION

110 E State Rd, West Grove, PA 19390

HSA PROJECT # :26-004

[redacted] HSA
Heckendorn Shiles Architects

PROJECT TEAM

CLIENT
Avon Grove Charter School
110 E State Rd
West Grove, PA 19390
484-667-5000

ARCHITECTURAL
Heckendorn Shiles Architects
347 East Conestoga Road
Wayne, PA 19087
610-994-3500

STRUCTURAL
Omdorf & Associates, Inc
8600 West Chester Pike, Suite 201
Upper Darby, PA 19802

MEPFP
Schiller & Hersh Associates, Inc.
636 Skippack Pike, Suite 200
Blue Bell, PA 19422
215-886-8947

NOT FOR CONSTRUCTION

KEYPLAN

PLAN NORTH


LEGEND
- OUT OF ARCHITECTURAL SCOPE
- SECTOR DESIGNATION
- MISC ITEM AS NEEDED
- MISC ITEM AS NEEDED

ISSUE HISTORY

Δ	DATE	ISSUED FOR
1	11-09-2026	BID ISSUE

SHEET TITLE
CODE ABSTRACT / INTERIOR SIGNAGE PLAN

DRAWING NUMBER
A002



1 A003 SITE STAGING PLAN
1/16" = 1'-0"

SHEET NOTES

1. REFER TO **SHEET A001** FOR ADDITIONAL DEMOLITION NOTES.
2. THIS PLAN IS MEANT TO OUTLINE THE GENERAL SCOPE OF STAGING FOR THE CONTRACTORS. THE SPECIFIC AREAS, ITEMS, DETAILS, EXTENT, ETC. WILL BE A RESULT OF COORDINATION OF ALL PRIME CONTRACTORS.
3. STAGING PLAN PROVIDED FOR REFERENCE, EXACT LAYOUT TO BE DETERMINED DURING PRECONSTRUCTION.
4. GC RESPONSIBLE FOR PROVIDING UPDATED STAGING PLAN AS PART OF PREVONSTRUCTION PHASE
5. GC TO PROVIDE PORTABLE TOILETS FOR THE DURATION OF THE PROJECT, FINAL LOCATION TO BE VERIFIED WITH OWNER PRIOR TO ONSITE CONSTRUCTION START
6. GC TO PROVIDE SECURED FENCING AROUND STAGING AREAS IDENTIFIED.
7. LAYDOWN AREA AND DUMPSTER RESTRICTIONS SHOWN FOR PHASE 1. ADDITIONAL LAYDOWN AREA IN PARKING LOT CAN BE AVAILABLE DURING PHASE 2 IF REQUIRED, BUT WILL REQUIRE FURTHER COORDINATION WITH OWNER.
8. DAMAGE TO GRASS REQUIRES REGRADING AND RESEEDING BY PRIME THAT CREATED THE DAMAGE.
9. TRAFFIC FLOW THROUGH PARKING LOTS MUST BE MAINTAINED
10. CRANES/HOISTS - PRIMES RESPONSBISIBLE FOR CRANES/HOISTS AS REQUIRED. PLANS FOR CRANES MUST BE REVIEWED AND APPROVED BY OWNER. PRIME RESPONSIBLE FOR PROTECTION OF SITE CONDITIONS AS WELL AS SAFETY ADN NOTIFICATION OF TRAFFIC/KIDS. CRANES MUST BE SCHEDULED TO HAVE NO IMPACT SCHOOL OPERATIONS.
11. TEMPORARY PARTITION TO REMAIN IN PLACE UNTIL PHASE 2.
12. PHASING PROVIDED TO ENSURE SCHOOL OPERATIONS ARE MINIMALLY IMPACTED. ITEMS NOTED AS PHASE 2 CANNOT START BEFORE DATES NOTED IN SPECIFICATION, UNLESS AGREED UPON BY OWNER.
    A. PHASE 1 - SCOPE OF PROJECT NOT NOTED IN PHASE 2.
    B. PHASE 2 - CANOPY DEMOLITION AND NEW CONSTRUCTION, EXTERIOR CONCRETE SLAB DEMOLITION AND NEW CONSTRUCTION, EXTERIOR HANDRAILS DEMOLITION, ROOF COPING REPLACEMENT, CORRIDOR CEILING REMOVAL AND REPLACEMENT.

AGCS STATE ROAD ADMINISTRATION

110 E State Rd, West Grove, PA 19390

HSA PROJECT # :26-004

HSA Heckendorn Shiles Architects

PROJECT TEAM

CLIENT
Avon Grove Charter School
110 E State Rd
West Grove, PA 19390
484-667-5000

ARCHITECTURAL
Heckendorn Shiles Architects
347 East Conestoga Road
Wayne, PA 19087
610-994-3500

STRUCTURAL
Omdorf & Associates, Inc
8600 West Chester Pike, Suite 201
Upper Darby, PA 19802

MEPFP
Schiller & Hersh Associates, Inc.
636 Skippack Pike, Suite 200
Blue Bell, PA 19422
215-886-8947

NOT FOR CONSTRUCTION

KEYPLAN

PLAN NORTH

LEGEND

- OUT OF ARCHITECTURAL SCOPE
- SECTOR DESIGNATION
- MISC ITEM AS NEEDED
- MISC ITEM AS NEEDED

ISSUE HISTORY

#	DATE	ISSUED FOR
1	11-09-2026	BID ISSUE

SHEET TITLE

PHASING/ STAGING PLANS

DRAWING NUMBER

A003

HECKENDORN SHILES ARCHITECTS expressly reserves its common law copyright and other property rights in these plans. These are not to be reproduced, nor are they to be assigned to any third party, without first obtaining the expressed written consent of HECKENDORN SHILES ARCHITECTS

11/10/2026 3:58:47 PM



9 A004 VIEW FROM ON ROOF OF CANOPY
1 1/2" = 1'-0"



6 A004 SIDE VIEW OF CANOPY
1 1/2" = 1'-0"



3 A004 ADMINISTRATION BRICK WALL
1 1/2" = 1'-0"



8 A004 WEST SIDE OF ENTRY WALL
1 1/2" = 1'-0"



5 A004 UNDERSIDE OF CANOPY, ENTRANCE ADN RAMP/STAIRS
1 1/2" = 1'-0"




2 A004 OVERVIEW IMAGE OF EXSTIGN CANOPY/ENTRANCE
1 1/2" = 1'-0"



7 A004 STRUCTURE AT CANOPY FROM RENOVATION IN 2009 - SHOWS EXISTING ROOF DRAIN
1 1/2" = 1'-0"



4 A004 STRUCTURE AT CANOPY FROM RENOVATION IN 2009
1 1/2" = 1'-0"



1 A004 PHOTOGRAPH KEY PLAN
1/32" = 1'-0"

AGCS STATE ROAD ADMINISTRATION

110 E State Rd, West Grove, PA 19390

HSA PROJECT # :26-004

[redacted] HSA
Heckendorn Shiles Architects

PROJECT TEAM

CLIENT
Avon Grove Charter School
110 E State Rd
West Grove, PA 19390
484-667-5000

ARCHITECTURAL
Heckendorn Shiles Architects
347 East Conestoga Road
Wayne, PA 19087
610-994-3500

STRUCTURAL
Omdorf & Associates, Inc
8600 West Chester Pike, Suite 201
Upper Darby, PA 19802

MEPFP
Schiller & Hersh Associates, Inc.
636 Skippack Pike, Suite 200
Blue Bell, PA 19422
215-886-8947

NOT FOR CONSTRUCTION

ISSUE HISTORY

Δ	DATE	ISSUED FOR
1	11-09-2026	BID ISSUE

SHEET TITLE
EXISTING PHOTOGRAPHS


DRAWING NUMBER
A004

HECKENDORN SHILES ARCHITECTS expressly reserves its common law copyright and other property rights in these plans. These are not to be reproduced, nor are they to be assigned to any third party, without first obtaining the expressed written consent of HECKENDORN SHILES ARCHITECTS

11/10/2026 3:58:52 PM




4 A005 BRICK RECESS WIDTH
1 1/2" = 1'-0"



2 A005 CLERESTORY GLAZING AND BRICK RECESSES
1 1/2" = 1'-0"



3 A005 BRICK RECESS DEPTH
1 1/2" = 1'-0"



1 A005 PHOTOGRAPH KEY PLAN
1/32" = 1'-0"

AGCS STATE ROAD ADMINISTRATION

110 E State Rd, West Grove, PA 19390

HSA PROJECT # :26-004

[redacted] HSA
Heckendorn Shiles Architects

PROJECT TEAM

CLIENT
Avon Grove Charter School
110 E State Rd
West Grove, PA 19390
484-667-5000

ARCHITECTURAL
Heckendorn Shiles Architects
347 East Conestoga Road
Wayne, PA 19087
610-994-3500

STRUCTURAL
Omdorf & Associates, Inc
8600 West Chester Pike, Suite 201
Upper Darby, PA 19802

MEPFP
Schiller & Hersh Associates, Inc.
636 Skippack Pike, Suite 200
Blue Bell, PA 19422
215-886-8947

NOT FOR CONSTRUCTION

ISSUE HISTORY

#	DATE	ISSUED FOR
1	11-09-2026	BID ISSUE

SHEET TITLE

EXISTING PHOTOGRAPHS

DRAWING NUMBER

A005

HECKENDORN SHILES ARCHITECTS expressly reserves its common law copyright and other property rights in these plans. These are not to be reproduced, nor are they to be assigned to any third party, without first obtaining the expressed written consent of HECKENDORN SHILES ARCHITECTS

11/10/2026 3:58:53 PM

1 AD101 EXISTING CONDITIONS & DEMOLITION - FIRST FLOOR PLAN
3/16" = 1'-0"

DEMOLITION PLAN SHEET NOTES

1. REFER TO **SHEET A001** FOR ADDITIONAL DEMOLITION NOTES.
2. REMOVE ALL WALL MOUNTED ITEMS AND ASSOCIATED HARDWARE WITHIN SCOPE OF WORK UNO. PROTECT FROM DAMAGE AND COORDINATE REINSTALLATION OF ITEMS WITH NEW CONSTRUCTION DRAWINGS. WALL MOUNTED ITEMS INCLUDE BUT IS NOT LIMITED TO:
   - A. **BLINDS**
   - B. **ROOM SIGNAGE**
   - C. **TOILET ACCESSORIES**
   - D. **WHITE BOARDS**
   - E. **TACK BOARDS**
   - F. **DISPLAY CASES**
   - G. **DOOR STOPS**
   - H. **SCREWS,**
   - I. **NAILS**
   - J. **EXPOSED HARDWARE**
   - K. **VINYL GRAPHICS**
3. REMOVE FINISHES TO A LEVEL SUITABLE FOR INSTALLATION OF NEW FINISHES, WHERE APPLICABLE. REFER TO NEW CONSTRUCTION DRAWINGS FOR ADDITIONAL INFORMATION.
4. FURNITURE REMOVAL **BY OWNER.**
5. AS REQUIRED, ANY DISRUPTED FIREPROOFING OF ALL BUILDING STRUCTURAL MEMBERS WALLS, FLOORS AND CEILING, SHALL BE SUPPLEMENTED AFTER DEMOLITION, IN ACCORDANCE WITH ALL CURRENTLY APPLICABLE CODES, REGULATION AND ORDINANCES OF ALL GOVERNING BODIES HAVING JURISDITION OVER THE PROJECT.
6. THIS PLAN IS MEANT TO OUTLINE THE GENERAL SCOPE OF DEMOLITION FOR THE CONTRACTORS. THE SPECIFIC AREAS, ITEMS, DETAILS, MATERIALS, EXTENT, ETC. OF DEMOLITION WILL BE A RESULT OF FIELD CONDITIONS. THE INTENT IS THAT ALL DEMOLITION REQUIRED TO PROPERLY CONSTRUCT THIS PROJECT IS THE RESPONSIBILITY OF THE PRIME CONTRACTORS. THE CONTRACTORS WILL ENSURE THE EXISTING BUILDING RETAINS STRUCTURAL INTEGRITY AND REMAINS WATER AND WEATHER-TIGHT DURING THE DEMOLITION AND CONSTRUCTION PHASES OF THE WORK.
7. UNDER-SLAB WORK INVOLVES THE GENERAL CONSTRUCTION (GC), PLUMBING (PC), AND ELECTRICAL (EC) PRIME CONTRACTORS. RESPONSIBILITIES ARE ASSIGNED AS FOLLOWS:
   1. **GC:** SAW CUT AND REMOVE THE EXISTING SLAB-ON-GRADE AS REQUIRED TO ACCOMMODATE THE UNDER-SLAB PLUMBING, ELECTRICAL AND STRUCTURAL WORK. PROTECT THE EXISTING CONSTRUCTION TO REMAIN.
   2. **GC:** AT NEW STEEL COLUMN LOCATIONS, EXPOSE THE EXISTING WALL FOOTING AND VERIFY ITS SIZE AND CONDITION IN THE FIELD BEFORE INSTALLING THE STEEL COLUMNS. REPORT ANY DISCREPANCIES WITH THE CONTRACT DOCUMENTS TO THE ARCHITECT IN WRITING. REFER TO DETAIL 1/S5.0.
   3. **PC AND EC:** EXCAVATE, INSTALL THE UNDER-SLAB PLUMBING AND ELECTRICAL WORK, AND BACKFILL TO SUBGRADE ELEVATION, IN ACCORDANCE WITH THE CONTRACT DOCUMENTS. COMPLETE ALL REQUIRED INSPECTIONS AND TESTING BEFORE BACKFILLING.
   4. **GC:** INSTALL A 10 MIL VAPOR BARRIER AND THE NEW CONCRETE SLAB, TIED INTO THE EXISTING SLAB, AS INDICATED ON THE STRUCTURAL DRAWINGS. MATCH THE EXISTING SLAB ELEVATION AND FINISH.

   THE PRIME CONTRACTORS SHALL COORDINATE THE EXTENT, LOCATION, AND SEQUENCE OF THEIR WORK WITH EACH OTHER. REFER TO DIVISION 01 FOR MULTIPLE-PRIME CONTRACT RESPONSIBILITIES.

SHEET KEYNOTES

(XXX) = KEYNOTE TAG

01 REMOVE EXISTING CAST IN PLACE SIDEWALK
02 REMOVE EXISTING CONCRETE RAMP AND HANDRAILS
03 REMOVE EXISTING CANOPY AND SUPPORT STRUCTURE. SEE DEMOLITION RCP / DEMOLITION ROOF PLAN FOR ADDITIONAL SCOPE
04 REMOVE EXISTING WALL PTAC UNITS, AND PROVIDE WEATHER TIGHT INFILL OF SIMILAR THERMAL VALUE. PROVIDE TEMP PROTECTION FROM THE ELEMENTS DURING CONSTRUCTION
05 EXISTING PANELS TO REMAIN AND BE PROTECTED DURING DEMOLITION. SEE MEPFP FOR ADDITIONAL INFORMATION.
06 EXISTING PANELS AND CONDUIT TO BE REMOVED. SEE MEPFP FOR ADDITIONAL INFORMATION.
07 EXISTING FLOOR HATCH TO CRAWL SPACE TO BE REMOVED.
08 REMOVE PTD WOOD COVER PIPE ENCLOSURE
09 REMOVE PLUMBING FIXTURES, REFER TO PLUMBING DWGS FOR ADDITIONAL INFORMATION
10 REMOVE EXISTING VCT FLOOR FINISH. COORDINATE EXTENTS WITH NEW PARTITIONS AND NEW CONSTRUCTION FINISH PLAN
11 REMOVE EXISTING FLOOR FINISH THROUGHOUT
12 REMOVE CASEWORK (BASE CABINETS AND UPPER CABINETS, AND COUNTERTOP
13 REMOVE DOOR AND FRAME
14 REMOVAL EXISTING TRANSOM WINDOWS OVERHEAD BY ABATEMENT CONTRACTOR. REFER TO AD200 FOR ADDITIONAL INFORMATION.
15 REMOVE WALL HUNG CASEWORK OPEN SHELVING
16 EXTENT OF EXISTING BLOCK / PARTITION WALL TO REMAIN
17 REMOVAL OF EXISTING WINDOW BY ABATEMENT CONTRACTOR
18 REMOVE EXISTING BLOCK WALL
19 REMOVE EXISTING BRICK MASONRY LOAD BEARING WALL. REFER TO STRUCTURAL DWGS FOR ADDITIONAL INFORMATION.
20 REMOVE EXISTING METAL LATHE AND PLASTER WALLS THROUGHOUT
21 REMOVE VESTIBULE WALK OFF CARPET
30 EXISTING CR TO BE PROTECTED. REMOVE / INSTALL AS REQUIRED FOR NEW WALL FINISH
31 LOCATION OF EXISTING EXTERIOR GRILL. PRIME CONTRACTOR TO FIELD VERIFY CONNECTION TO EXISTING INFRASTRUCTURE AND NOTIFY ARCHITECT. PROVIDE WEATHER TIGHT INFILL OF SIMILAR THERMAL VALUE. FINISH FACE TO MATCH SURROUNDING EXTERIOR WALL
32 REMOVE CONCRETE SLAB FOR NEW ACCESS HATCH. COORDINATE LOCATION WITH CONSTRUCTION PLAN

AGCS STATE ROAD ADMINISTRATION

110 E State Rd, West Grove, PA 19390

HSA PROJECT # :26-004

[redacted] HSA
Heckendorn Shiles Architects

PROJECT TEAM

CLIENT
Avon Grove Charter School
110 E State Rd
West Grove, PA 19390
484-667-5000


ARCHITECTURAL
Heckendorn Shiles Architects
347 East Conestoga Road
Wayne, PA 19087
610-994-3500

STRUCTURAL
Orndorf & Associates, Inc
8600 West Chester Pike, Suite 201
Upper Darby, PA 19802

MEPFP
Schiller & Hersh Associates, Inc.
636 Skippack Pike, Suite 200
Blue Bell, PA 19422
215-886-8947

NOT FOR CONSTRUCTION

KEYPLAN



LEGEND

OUT OF ARCHITECTURAL SCOPE

ISSUE HISTORY

Δ	DATE	ISSUED FOR
1	11-09-2026	BID ISSUE

SHEET TITLE


EXISTING CONDITIONS & DEMOLITION - FIRST FLOOR PLAN

DRAWING NUMBER

AD101

11/10/2026 3:58:55 PM
HECKENDORN SHILES ARCHITECTS expressly reserves its common law copyright and other property rights in these plans. These are not to be reproduced, nor are they to be assigned to any third party, without first obtaining the expressed written consent of HECKENDORN SHILES ARCHITECTS

11/10/2026 3:58:58 PM HECKENDORN SHILES ARCHITECTS expressly reserves its common law copyright and other property rights in these plans. These are not to be reproduced, nor are they to be assigned to any third party, without first obtaining the expressed written consent of HECKENDORN SHILES ARCHITECTS



1 AD102 EXISTING CONDITIONS AND DEMOLITION - ROOF PLAN
3/16" = 1'-0"

SHEET KEYNOTES

XXX = KEYNOTE TAG

03 REMOVE EXISTING CANOPY AND SUPPORT STRUCTURE. SEE DEMOLITION RCP / DEMOLITION ROOF PLAN FOR ADDITIONAL SCOPE
22 REMOVE ROOF DRAIN
23 COORDINATE REMOVAL OF EXISTING CANOPY ROOF MEMBRANE TO ALLOW FOR FUTURE REINSTALLATION OF PARAPET / ROOF MEMBRANE
24 REMOVE EXISTING COPING
25 REMOVE ROOF CAP AND CURB. SEE ROOF PATCHING DETAILS. REFER TO MECH DWGS. FOR ADDL INFORMATION
28 PROVIDE NEW OPENING IN SIDE OF EXISTING BRICK WALL FOR NEW DRAIN PATHS. SEE ELEVATIONS FOR ADDL INFORMATION.
29 REMOVE EXISTING GUTTER

AGCS STATE ROAD ADMINISTRATION

110 E State Rd, West Grove, PA 19390

HSA PROJECT # :26-004

[redacted] HSA
Heckendorn Shiles Architects

PROJECT TEAM

CLIENT
Avon Grove Charter School
110 E State Rd
West Grove, PA 19390
484-667-5000


ARCHITECTURAL
Heckendorn Shiles Architects
347 East Conestoga Road
Wayne, PA 19087
610-994-3500

STRUCTURAL
Omdorf & Associates, Inc
8600 West Chester Pike, Suite 201
Upper Darby, PA 19802

MEPFP
Schiller & Hersh Associates, Inc.
636 Skippack Pike, Suite 200
Blue Bell, PA 19422
215-886-8947

NOT FOR CONSTRUCTION

KEYPLAN



LEGEND

OUT OF ARCHITECTURAL SCOPE

ISSUE HISTORY


#	DATE	ISSUED FOR
1	11-09-2026	BID ISSUE

SHEET TITLE


EXISTING CONDITIONS & DEMOLITION - ROOF PLAN

DRAWING NUMBER

AD102



2 AD110 EXISTING CONDITIONS & DEMOLITION - RCP - ALTERNATE SCOPE
3/16" = 1'-0"



1 AD110 EXISTING CONDITIONS & DEMOLITION - RCP - BASE SCOPE
3/16" = 1'-0"

DEMOLITION RCP PLAN SHEET NOTES

1. THIS PLAN IS MEANT TO OUTLINE THE GENERAL SCOPE OF DEMOLITION FOR THE CONTRACTORS. THE SPECIFIC AREAS, ITEMS, DETAILS, MATERIALS, EXTENT, ETC. OF DEMOLITION WILL BE A RESULT OF FIELD CONDITIONS. THE INTENT IS THAT ALL DEMOLITION REQUIRED TO PROPERLY CONSTRUCT THIS PROJECT IS THE RESPONSIBILITY OF THE PRIME CONTRACTORS. THE CONTRACTORS WILL ENSURE THE EXISTING BUILDING RETAINS STRUCTURAL INTEGRITY AND REMAINS WATER AND WEATHER-TIGHT DURING THE DEMOLITION AND CONSTRUCTION PHASES OF THE WORK.

SHEET KEYNOTES

(XXX) = KEYNOTE TAG

1	BASE SCOPE: RETAIN EXISTING CORRIDOR LIGHTING AND CEILING GRID. REMOVE EXISTING ACT TILES AND ADJUST EXISTING GRID AND EXISTING DEVICES TO PREPARE FOR NEW CONSTRUCTION.
2	ALTERNATE SCOPE: REMOVE EXISTING CORRIDOR LIGHTING, CEILING GRID, ACT AND CEILING DEVICES ENTIRELY. SEE ALTERNATE NEW CONSTRUCTION RCP.
3	REMOVE EXISTING CEILING MOUNTED CABINET UNIT HEATER. SEE MEPFP DRAWINGS FOR NEW LOCATION.
4	REMOVE EXISTING CEILINGS, GRID, LIGHT FIXTURES AND CEILING DEVICES
5	CARD READER AND CAMERA TO BE RELOCATED. COORDINATE WITH NEW EXTERIOR WALL FINISH
6	REMOVE EXISTING LIGHTING FIXTURES. SEE ELECTRICAL FOR ADDITIONAL INFORMATION
7	REMOVE, STORE AND REINSTALL EXISTING CEILING DEVICES. SEE ELECTRICAL DRAWINGS FOR ADDITONAL INFORMATION
8	LINE OF EXISTING STRUCTURAL STEEL TO BE PROTECTED DURING DEMOLITION.
9	REMOVE EXISTING FASCIA AND SOFFIT AND SUB FRAMING BACK TO STOREFRONT
10	REMOVE EXISTING CANOPY AND STRUCTURE, REMOVE COLUMNS DOWN TO BELOW GRADE. COORDINATE DEMOLITION EXTENTS WITH NEW CONSTRUCTION.

AGCS STATE ROAD ADMINISTRATION

110 E State Rd, West Grove, PA 19390

HSA PROJECT # :26-004

Heckendorn Shiles Architects

PROJECT TEAM

CLIENT
Avon Grove Charter School
110 E State Rd
West Grove, PA 19390
484-667-5000


ARCHITECTURAL
Heckendorn Shiles Architects
347 East Conestoga Road
Wayne, PA 19087
610-994-3500

STRUCTURAL
Omdorf & Associates, Inc
8600 West Chester Pike, Suite 201
Upper Darby, PA 19802

MEPFP
Schiller & Hersh Associates, Inc.
636 Skippack Pike, Suite 200
Blue Bell, PA 19422
215-886-8947

NOT FOR CONSTRUCTION

KEYPLAN



LEGEND

- OUT OF ARCHITECTURAL SCOPE
- SECTOR DESIGNATION
- MISC ITEM AS NEEDED
- MISC ITEM AS NEEDED

ISSUE HISTORY

#	DATE	ISSUED FOR
1	11-09-2026	BID ISSUE


SHEET TITLE

EXISTING CONDITIONS & DEMOLITION - FIRST FLOOR RCP


DRAWING NUMBER

AD110


11/10/2026 3:58:59 PM HECKENDORN SHILES ARCHITECTS expressly reserves its common law copyright and other property rights in these plans. These are not to be reproduced, nor are they to be assigned to any third party, without first obtaining the expressed written consent of HECKENDORN SHILES ARCHITECTS




6 AD200 EXISTING CANOPY CROSS SECTION
3/16" = 1'-0"




5 AD200 EXISTING SECTOR A CROSS SECTION
3/16" = 1'-0"




4 AD200 EXISTING SECTOR B CROSS SECTION
3/16" = 1'-0"



3 AD200 OVERALL EXISTING LONGITUDINAL BUILDING SECTION
3/16" = 1'-0"



2 AD200 DEMO WEST ELEVATION
3/16" = 1'-0"



1 AD200 EXISTING CONDITIONS & DEMOLITION SOUTH EXTERIOR ELEVATION
3/16" = 1'-0"

1. BUILDING SECTIONS PROVIDED FOR REFERNCE TO INDICATE EXISTING HEIGHTS AND TRANSITIONS.

2. ALL EXISTING DIMENSIONS TO BE FIELD VERIFIED

SHEET KEYNOTES

(XX) = KEYNOTE TAG

04	REMOVE EXISTING WALL PTAC UNITS, AND PROVIDE WEATHER TIGHT INFILL OF SIMILAR THERMAL VALUE. PROVIDE TEMP PROTECTION FROM THE ELEMENTS DURING CONSTRUCTION
14	REMOVAL EXISTING TRANSOM WINDOWS OVERHEAD BY ABATEMENT CONTRACTOR. REFER TO AD200 FOR ADDITIONAL INFORMATION.
17	REMOVAL OF EXISTING WINDOW BY ABATEMENT CONTRACTOR
22	REMOVE ROOF DRAIN
24	REMOVE EXISTING COPING
26	REMOVE, PROTECT AND STORE LETTERING FOR REINSTALLATION
31	LOCATION OF EXISTING EXTERIOR GRILL. PRIME CONTRACTOR TO FIELD VERIFY CONNECTION TO EXISTING INFRASTRUCTURE AND NOTIFY ARCHITECT. PROVIDE WEATHER TIGHT INFILL OF SIMILAR THERMAL VALUE. FINISH FACE TO MATCH SURROUNDING EXTERIOR WALL

AGCS STATE ROAD ADMINISTRATION

110 E State Rd, West Grove, PA 19390

HSA PROJECT # :26-004

[redacted] HSA
Heckendorn Shiles Architects

PROJECT TEAM

CLIENT
Avon Grove Charter School
110 E State Rd
West Grove, PA 19390
484-667-5000

ARCHITECTURAL
Heckendorn Shiles Architects
347 East Conestoga Road
Wayne, PA 19087
610-994-3500

STRUCTURAL
Omdorf & Associates, Inc
8600 West Chester Pike, Suite 201
Upper Darby, PA 19802

MEPFP
Schiller & Hersh Associates, Inc.
636 Skippack Pike, Suite 200
Blue Bell, PA 19422
215-886-8947

NOT FOR CONSTRUCTION

LEGEND

OUT OF ARCHITECTURAL SCOPE

ISSUE HISTORY

Δ	DATE	ISSUED FOR
1	11-09-2026	BID ISSUE

SHEET TITLE


EXISTING CONDITIONS & DEMO - EXT. ELEV'S AND SECTIONS

DRAWING NUMBER

AD200

HECKENDORN SHILES ARCHITECTS reserves its common law copyright and other property rights in these plans. These are not to be reproduced, nor are they to be assigned to any third party, without first obtaining the expressed written consent of HECKENDORN SHILES ARCHITECTS

11/10/2026 3:59:01 PM



1 A101 NEW CONSTRUCTION - FIRST FLOOR PLAN
3/16" = 1'-0"

NEW CONSTRUCTION SHEET NOTES

1. REFER TO **SHEET A001** FOR ADDITIONAL NEW CONSTRUCTION NOTES.
2. REFER TO A600 FOR PARTITION SCHEDULE
3. REFER TO A601 FOR DOOR AND FRAME SCHEDULE
4. ALL DIMENSIONS ARE **TO FINISHED FACE**, UNO.
5. ALL EXTERIOR WALL AND ROOF PENETRATIONS TO BE MADE BY GC. REFER TO MECHANICAL, PLUMBING AND ELECTRICAL DRAWINGS FOR PENETRATIONS REQUIRED. MC, PC AND EC TO PROVIDE FINAL SIZE AND LAYOUT ON SITE FOR GC COORDINATION. REFER TO A500 SERIES FOR TYPICAL DETAILS.
6. ALL INTERIOR WALL PENETRATIONS TO BE MADE BY PRIME CONTRACTOR REQUIRING THE PENETRATION, UNO. EACH PRIME IS RESPONSIBLE FOR PROTECTION OF EXISTING CONDITIONS TO REMAIN (INCLUDNG BUT NOT LIMITED TO FLOORING, WALLS, FURNITURE).
7. PATCH/FILL/REPAIR ALL EXISTING PARTITIONS WITHIN SCOPE OF WORK WHERE MEP/FP DEVICES HAVE BEEN REMOVED AND WHERE A PORTION OF WALL HAS BEEN REMOVED FOR A NEW MEP/FP DEVICE, INCLUDING BUT NOT LIMITED TO PANELS, ATTACHMENTS, FIXTURES AND DEVICES, U.N.O. COORDINATE LOCATIONS WITH MEP/FP CONTRACTORS AND REFER TO MEP/FP DWGS FOR ADDITIONAL INFO
8. PREP ALL SURFACES FOR NEW FINISH, COORDINATE FINISHES WITH **A12 SERIES FINISH DRAWINGS**.
9. EXISTING FLOOR SLAB SHALL BE PATCHED, REPAIRED, REFINISHED AND LEVELED AS REQUIRED TO RECEIVE NEW FINISH MATERIALS.
10. FIRE EXTINGUISHER NOTE:
    A. UTILIZE EXISTING/RELOCATE SEMI-RECESSED FIRE EXTINGUISHERS/CABINETS AS REQUIRED BY CODE. GC TO PROVIDE NEW.
    B. (NEW.) ALL FIRE EXTINGUISHERS/CABINETS ARE NEW. PROVIDE AND INSTALL NEW BUILDING STANDARD SEMI-RECESSED FIRE EXTINGUISHERS. CABINETS AS INDICATED AND REQUIRED B CODE. PROVIDE AN INSTALL 'FIRE EXTINGUISHER' STAND-OUT SIGNS ARE REQUIRED BY CODE ABOVE CABINET. (SPECIFICATION: BROOKS EQUIPMENT CO., INC. PTD182 'FIRE EXTINGUISHER' STAND-OUT SIGN)
11. PROVIDE AND INSTALL ADA COMPLIANT WALL-MOUNTED EXIT SIGNS (TACTILE) AT EACH EXIT DOOR AS REQUIRED TO MEET ADA, LIFE SAFETY CODE, AND ALL APPLICABLE LOCAL CODES.
12. PROVIDE SS-1 WINDOW STOOLS AT ALL NEW STOREFRONT OPENINGS.
13. GC TO PATCH/REPAIR CONCRETE FLOOR SLAB AT LOCATIONS OF REMOVED/CAPPED PLUMBING FIXTURES DRAIN LINES.

SHEET KEYNOTES

(XXX) = KEYNOTE TAG

01 CASEWORK, BASE CABINETS WITH COUNTER
02 CASEWORK, FULL HEIGHT CABINET
03 CASEWORK - BASE CABINETS AND OPEN COUNTER
04 PRINTER EQUIPMENT COORDINATE ELECTRICAL AND TELE/DATA REQUIREMENTS
05 CASEWORK - BASE CABINET, COUNTER WITH SINK, UPPER CABINETS
06 MAIL SORTING FURNITURE BY OWNER
07 PROVIDE 24'X24' REMOVABLE FLOOR HATCH FOR CONCRETE W/ RECESS TO RECIEVE CARPET. COORDINATE FINAL LOCATION WITH EXISTING STRUCTURE BELOW. INSTALL INTO EXISTING CRAWL SPACE. COORDINATE INSTALLATION OF FLOOR FINISH INTO ACCESS PANEL RESINFORCE SLAB AND DECK PRIOR TO CUTTING, REFER TO STRUCTURAL DWGS FOR ADD'L INFO
08 INFILL EXISTING ACCESS HOLE WITH CONCRETE COMPOSITE SLAB FLUSH TO EXISTING CONCRETE SLAB. PROVIDE C6 BELOW ANCHERSED TO EXISTIGN STRUTURE. PROVIDE 4 1/2" NORLA WEIGHT CONCRETE W/ 6X6-W2.1 X S2.1 WWF ON 3", 20 GA COMPOSITE METAL DECK
09 INSTALL ADA PUSHBUTTON TO OPERATE EXISTING AUTO OPERATOR,
AT BUBBLED MAIN ENTRANCE DOUBLE DOORS.
COORDINATE WITH ELECTRICAL
TO CAPTURE INTENT AND SECURITY VENDOR, INSTALLER
10 CLEAR ANNODIZED ALUMINUM STOREFRONT SYSTEM W/ 1" INSULATED GLAZING. REFER TO ENLARGED ELEVATIONS FOR ADD'L INFO. BOD: YKK YES 45 TU
11 SLOPED CONCRETE SLAB, OVERBUILT OVER EXISTING STAIRS. DOWEL TO EXISTING STAIR , PROVIDE 4" CONCRETE ON 4" 2B STONE BASE, UNO.
12 PROVIDE GWB ON 7/8" HAT CHANNELS ON THIS WALL
13 GC TO PATCH/REPAIR CONCRETE SLAB AT LOCATION OF PLUMBING TRENCH. PC TO BACKFILL AND COMPACT SOIL, GC TO PROVIDE VAPOR BARRIER, STONE AND CONCRETE PER STRUCTURAL DETAIL.
14 GC PATCH/REPAIR CONCRETE SLAB AT LOCATION OF MASONRY WALL REMOVAL. GC TO BACKFILL AND COMPACT SOIL, PROVIDE STONE, VAPOR BARRIER AND CONCRETE PER STRUCTURAL DETAIL.
49 PATCH ALL EXISTING RAILING PENETRATIONS WITH NON SHRINK GROUT FLUSH TO ADJACENT CONCRETE
50 ADD ALTERNATE: BOLLARDS SPACED 5'-0" O.C., 18" INBOUND OF CURB LINE. SEE A505 FOR DETAILS
51 GWB CASED OPENING
52 EXPOSED ARCHITECTRAL CONCRETE PIER WITH STRUCTURAL STEEL V-COLUMN. STEEL TO BE HOT DIP GALVANIZED FACTORY APPLIED POWDER COATED STEEL. BD FOR FINISH: COLORGAV THERMOSET
55 PROVIDE CASEWORK OPEN SHELVING

AGCS STATE ROAD ADMINISTRATION

110 E State Rd, West Grove, PA 19390

HSA PROJECT # :26-004

[redacted] HSA
Heckendorn Shiles Architects

PROJECT TEAM

CLIENT
Avon Grove Charter School
110 E State Rd
West Grove, PA 19390
484-667-5000


ARCHITECTURAL
Heckendorn Shiles Architects
347 East Conestoga Road
Wayne, PA 19087
610-994-3500

STRUCTURAL
Omdorf & Associates, Inc
8600 West Chester Pike, Suite 201
Upper Darby, PA 19802

MEPFP
Schiller & Hersh Associates, Inc.
636 Skippack Pike, Suite 200
Blue Bell, PA 19422
215-886-8947

NOT FOR CONSTRUCTION

KEYPLAN



LEGEND

OUT OF ARCHITECTURAL SCOPE

ISSUE HISTORY

#	DATE	ISSUED FOR
1	11-09-2026	BID ISSUE

SHEET TITLE


NEW CONSTRUCTION PLAN

DRAWING NUMBER


A101

HECKENDORN SHILES ARCHITECTS expressly reserves its common law copyright and other property rights in these plans. These are not to be reproduced, nor are they to be assigned to any third party, without first obtaining the expressed written consent of HECKENDORN SHILES ARCHITECTS

11/10/2026 3:59:04 PM



2 A102 NEW CONSTRUCTION - LOW ROOF PLAN
3/16" = 1'-0"



1 A102 NEW CONSTRUCTION - ROOF PLAN
3/16" = 1'-0"

NEW CONSTRUCTION SHEET NOTES

1. REFER TO **SHEET A001** FOR ADDITIONAL NEW CONSTRUCTION NOTES.
2. REFER TO A600 FOR PARTITION SCHEDULE
3. REFER TO A601 FOR DOOR AND FRAME SCHEDULE
4. ALL DIMENSIONS ARE **TO FINISHED FACE**, UNO.
5. ALL EXTERIOR WALL AND ROOF PENETRATIONS TO BE MADE BY GC. REFER TO MECHANICAL, PLUMBING AND ELECTRICAL DRAWINGS FOR PENETRATIONS REQUIRED. MC, PC AND EC TO PROVIDE FINAL SIZE AND LAYOUT ON SITE FOR GC COORDINATION. REFER TO A500 SERIES FOR TYPICAL DETAILS.
6. ALL INTERIOR WALL PENETRATIONS TO BE MADE BY PRIME CONTRACTOR REQUIRING THE PENETRATION, UNO. EACH PRIME IS RESPONSIBLE FOR PROTECTION OF EXISTING CONDITIONS TO REMAIN (INCLUDNG BUT NOT LIMITED TO FLOORING, WALLS, FURNITURE).
7. PATCH/FILL/REPAIR ALL EXISTING PARTITIONS WITHIN SCOPE OF WORK WHERE MEP/FP DEVICES HAVE BEEN REMOVED AND WHERE A PORTION OF WALL HAS BEEN REMOVED FOR A NEW MEP/FP DEVICE, INCLUDING BUT NOT LIMITED TO PANELS, ATTACHMENTS, FIXTURES AND DEVICES, U.N.O. COORDINATE LOCATIONS WITH MEP/FP CONTRACTORS AND REFER TO MEP/FP DWGS FOR ADDITIONAL INFO
8. PREP ALL SURFACES FOR NEW FINISH, COORDINATE FINISHES WITH **A12 SERIES FINISH DRAWINGS**.
9. EXISTING FLOOR SLAB SHALL BE PATCHED, REPAIRED, REFINISHED AND LEVELED AS REQUIRED TO RECEIVE NEW FINISH MATERIALS.
10. FIRE EXTINGUISHER NOTE:
    A. UTILIZE EXISTING/RELOCATE SEMI-RECESSED FIRE EXTINGUISHERS/CABINETS AS REQUIRED BY CODE. GC TO PROVIDE NEW.
    B. (NEW) ALL FIRE EXTINGUISHERS/CABINETS ARE NEW. PROVIDE AND INSTALL NEW BUILDING STANDARD SEMI-RECESSED FIRE EXTINGUISHERS. CABINETS AS INDICATED AND REQUIRED B CODE. PROVIDE AN INSTALL "FIRE EXTINGUISHER" STAND-OUT SIGNS ARE REQUIRED BY CODE ABOVE CABINET. (SPECIFICATION: BROOKS EQUIPMENT CO., INC. PTD182 "FIRE EXTINGUISHER" STAND-OUT SIGN)
11. PROVIDE AND INSTALL ADA COMPLIANT WALL-MOUNTED EXIT SIGNS (TACTILE) AT EACH EXIT DOOR AS REQUIRED TO MEET ADA, LIFE SAFETY CODE, AND ALL APPLICABLE LOCAL CODES.
12. PROVIDE SS-1 WINDOW STOOLS AT ALL NEW STOREFRONT OPENINGS.
13. GC TO PATCH/REPAIR CONCRETE FLOOR SLAB AT LOCATIONS OF REMOVED/CAPPED PLUMBING FIXTURES DRAIN LINES.

SHEET KEYNOTES

(X00) = KEYNOTE TAG

16 NEW DEDICATED OUTDOOR AIR UNIT ON 18" HIGH ROOF CURB FURNISHED BY MC. GC TO PROVIDE ROOF OPENING AND FRAMING PER STRUCTURAL (1/S5.1, 2/S5.1), AND ROOFING AND CURB FLASHING PER 15/A506. REFER TO MECHANICAL DRAWINGS FOR UNIT, SIZE AND LOCATION PROVIDE PT BLOCKING FOR LEVELING CURBS AND RAILS. COORDINATE ROOF CRICKETS TO DIVERT WATER AROUND CURBS/SUPPORTS/EQUIPMENT AS REQUIRED. SEAL ROOF PER ROOF PENETRATION DETAILS.

17 NEW OUTDOOR HEAT RECOVERY UNIT ON EQUIPMENT RAILS PER 17/A506. SUPPORT PER STRUCTURAL DRAWINGS. REFER TO MECHANICAL DRAWINGS FOR UNIT AND LOCATION.

18 REFRIGERANT PIPING AND CONDUIT PENETRATIONS SERVING ROOFTOP EQUIPMENT. FLASH PER 4/A506 OR 13/A506 AS APPLICABLE. MC AND EC TO COORDINATE LOCATIONS WITH GC.

19 PLUMBING VENT THROUGH ROOF. GC TO PROVIDE OPENING AND FLASHING PER 14/A506 AND 11/A506. REFER TO PLUMBING DRAWINGS.

20 NEW EXHAUST FAN ON ROOF CURB FURNISHED BY MC. GC TO PROVIDE ROOF OPENING, FRAMING PER STRUCTURAL, AND CURB FLASHING PER 15/A506. REFER TO MECHANICAL DRAWINGS.

21 NEW GRAVITY VENTILATOR ON ROOF CURB FURNISHED BY MC. GC TO PROVIDE ROOF OPENING, FRAMING PER STRUCTURAL, AND CURB FLASHING PER 15/A506. REFER TO MECHANICAL DRAWINGS.

22 PATCH ROOF AT REMOVED ROOF CAP AND CURB (AD102 KEYNOTE 25). INFILL DECK OPENING TO MATCH EXISTING CONSTRUCTION. PROVIDE INSULATION AND EPDM TO MATCH ADJACENT ROOF, TIED INTO EXISTING PER 3/A506.

23 EXISTING ROOFTOP EQUIPMENT TO REMAIN. PROTECT ROOF AND EQUIPMENT DURING CONSTRUCTION.

24 NEW CANOPY ROOF: EPDM ROOFING ON EXTERIOR SHEATHING OVER METAL DECK, SLOPED AS SHOWN. REFER TO 4/A300, 4/A402 AND STRUCTURAL DRAWINGS.

25 CANOPY ROOF EDGE: PHENOLIC PANEL FASCIA WITH FASCIA COVER AND 24 GA GALVANIZED STEEL WATERDAM PER 5/A402.

26 TIE NEW EPDM ROOFING INTO EXISTING ROOF SYSTEM PER 3/A506 AND 12/A506.

27 NEW ROOF DRAIN AND OVERFLOW DRAIN PER 7/A506, 8/A506 AND 20/A506. RAINWATER CONDUCTOR ROUTED TO EXTERIOR THROUGH NEW OPENING IN EXISTING BRICK WALL (AD102 KEYNOTE 36). REFER TO ELEVATIONS. REFER TO PLUMBING DWGS FOR ADDL INFO.

28 NEW METAL COPING TO MATCH METAL WALL PANEL, EXTENDED FOR NEW WALL THICKNESS, PER 2/A506. PARAPET AT METAL PANEL PER 1/A506.

29 REINSTALL PARAPET AND ROOF MEMBRANE AT EXISTING CANOPY ROOF

30 PROVIDE TAPERED INSULATION CRICKETS TO DIRECT WATER TO ROOF DRAIN AND OVERFLOW DRAIN. SLOPE 1/2" PER FOOT MIN. REFER TO 7/A506, 8/A506 AND 20/A506

53 STOP / START POINT OF METAL PANEL AT ROOF WING WALLS

AGCS STATE ROAD ADMINISTRATION

110 E State Rd, West Grove, PA 19390

HSA PROJECT # :26-004

[redacted] HSA
Heckendorn Shiles Architects

PROJECT TEAM

CLIENT
Avon Grove Charter School
110 E State Rd
West Grove, PA 19390
484-667-5000


ARCHITECTURAL
Heckendorn Shiles Architects
347 East Conestoga Road
Wayne, PA 19087
610-994-3500

STRUCTURAL
Omdorf & Associates, Inc
8600 West Chester Pike, Suite 201
Upper Darby, PA 19802

MEPFP
Schiller & Hersh Associates, Inc.
636 Skippack Pike, Suite 200
Blue Bell, PA 19422
215-886-8947

NOT FOR CONSTRUCTION

KEYPLAN



LEGEND

OUT OF ARCHITECTURAL SCOPE

ISSUE HISTORY

#	DATE	ISSUED FOR
1	11-09-2026	BID ISSUE


SHEET TITLE

NEW CONSTRUCTION ROOF PLAN


DRAWING NUMBER

A102

11/10/2026 3:58:06 PM
HECKENDORN SHILES ARCHITECTS expressly reserves its common law copyright and other property rights in these plans. These are not to be reproduced, nor are they to be assigned to any third party, without first obtaining the expressed written consent of HECKENDORN SHILES ARCHITECTS



1 A110 NEW CONSTRUCTION - REFLECTED CEILING PLAN - ALTERNATE SCOPE
3/16" = 1'-0"



2 A110 NEW CONSTRUCTION - REFLECTED CEILING PLAN - BASE SCOPE
3/16" = 1'-0"

SHEET NOTES

1. ALL DIMENSIONS **TO FINISHED FACE**, UNLESS NOTED OTHERWISE.
2. PAINT GWB CEILINGS AND UNDERSIDES OF SOFFITS UNO.
3. ALL IN SCOPE ROOMS RECEIVE CEILING TYPE ACT-1 UNO. SEE FINISH SCHEDULE AND SPECIFICATIONS FOR MORE INFORMATION.
4. **REFER TO A500** FOR CEILING TRANSITION DETAILS.
5. CEILING HEIGHTS ARE FROM THE FINISHED FLOOR.
6. CEILING TILES TO BE CENTERED IN ROOM, TYP, UNO.
7. ACT TILES SHALL NOT BE LESS THAN 4". NOTIFY ARCHITECT OF ANY DISCREPANCIES.
8. REFER TO **INTERIOR ELEVATIONS** FOR MOUNTING HEIGHTS OF WALL MOUNTED FIXTURES.
9. UNLESS NOTED OTHERWISE, CENTER ALL FIXTURES IN CEILING TILES.
10. AT EXPOSED TO STRUCTURE PAINTED LOCATIONS:
    A. COORDINATE FINAL PAINT SCOPE **WITH MEP/FP CONTRACTORS AND** THE ARCHITECT.
    B. PAINT SCOPE INCLUDES BUT IS NOT LIMITED TO THE FOLLOWING ITEMS.
        a. PAINT EXPOSED STRUCTURE, DECK, PIPING, DUCTS, INSULATION, LOUVERS, GRILLES, ACOUSTIC CEILINGS, CONDUIT.
11. REFER TO MEP/FP DRAWINGS FOR ADDITIONAL INFORMATION.
12. CENTER ALL EXIT SIGNS OVER DOOR OR OPENING, UNO.
13. COORDINATE GWB FRAMING AND GWB INSTALLATION W/ ALL MEPFP CEILING EQUIPMENT, FIXTURES, AND GRIDS.
14. ALL DIMENSIONS OF CEILING FIXTURES GIVEN TO CENTERLINE OF FIXTURE, UNO
15. ACOUSTICAL CEILING TILE SHALL BE CENTERED IN SPACE, AND NEVER TO HAVE A TILE CUT LESS THAN 4" WIDE
16. REFER TO ELEC DWG FOR LIGHT FIXTURE INFORMATION
17. REFER TO ELEC DWG FOR CEILING DEVICES AND COORDINATE INSTALLATION IN ACT AND GWB CEILINGS.
18. GC TO COORDINATE WITH AV VENDOR TO PROVIDE BLOCKING/BACKING AS NEEDED FOR MOUNTING OF CEILING MOUNTED DEVICES (INTERIOR AND/OR EXTERIOR).
19. MECHANICAL CEILING DEVICES ARE SHOWN FOR COORDINATION ONLY. REFER TO M101 AND M301 FOR TYPE, SIZE, QUANTITY AND CONNECTIONS. DEVICES SHOWN ON THE MECHANICAL DRAWINGS BUT NOT SHOWN HERE ARE STILL INCLUDED IN THE WORK.
20. BEFORE ROUGH IN, THE MC SHALL VERIFY CLEARANCE FOR ABOVE CEILING INFRASTRUCTURE AT CEILING HEIGHTS SHOWN AND REPORT CONFLICTS TO ARCHITECT.
21. THE MC FURNISHES ACCESS DOORS WHEREVER CEILING ACCESS IS REQUIRED FOR ABOVE CEILING INFRASTRUCTURE. GC TO INSTALL. LOCATIONS TO BE COORDINATED WITH ARCHITECT.

SHEET KEYNOTES

(X00) = KEYNOTE TAG

30 PROVIDE TAPERED INSULATION CRICKETS TO DIRECT WATER TO ROOF DRAIN AND OVERFLOW DRAIN. SLOPE 1/2" PER FOOT MIN. REFER TO 7/A506, 8/A506 AND 20/A506
31 LINE OF COLUMN BASE AT GRADE
32 SLOPING, PHENOLIC PANEL SOFFIT AP-1 ON HAT CHANNEL OVER LIGHT-GAUGE FRAMING. PANEL JOINTS AS SHOWN ON THE ENLARGED RCP. COORDINATE FIXTURE CUTOUTS SO NONE LAND ON A PANEL JOINT.
33 REFER TO ENLARGED RCP FOR ADDITIONAL INFORMATION
34 PROVIDE MANUAL ROLLER SHADE IN WT-1. SHADE BOX TO MATCH MULLION
35 PROVIDE NEW GWB AT STOREFRONT HEAD
36 OPEN TO STRUCTURE ABOVE. PAINT EXPOSED DECK, STRUCTURE, INFRASTRUCTURE (INCLUDING CONDUIT, PIPING, DUCTWORK, CABLING, TO BE PAINTED P.X
37 CEILING MOUNTED AV DISPLAY
38 PROVIDE UNDERCABINET LIGHTING
39 EXISTING CEILING GRID TO REMAIN. PROVIDE NEW ACT-1. ADJUST GRID AS REQUIRED AT NEW PARTITIONS. EXISTING LIGHT FIXTURES AND CEILING DEVICES REMOVED AND REINSTALLED IN THE SAME LOCATIONS; REFER TO E0101 AND E101.
40 ALTERNATE SCOPE: REMOVE EXISTING GRID AND TILE. PROVIDE NEW ACT-2 CEILING AT 8'-0" AFF WITH GWB SOFFIT AT THE SUITE WALL. REFER TO THE ALTERNATE RCP AND E101 FOR NEW FIXTURES.
41 ALTERNATE SCOPE: CONTINUOUS LINEAR LIGHT FIXTURE AT THE EDGE OF THE GWB SOFFIT. COORDINATE THE REVEAL WITH THE SOFFIT EDGE.
43 GWB SOFFIT AT 7'-6" AFF WITH RECESSED LINEAR FIXTURE CENTERED IN THE SOFFIT. COORDINATE THE DROP WITH STOREFRONT AND DOOR HEADS.
44 LINE OF SLOPE TRANSITION, FROM THE LEVEL SOFFIT TO THE SLOPING CANOPY.
45 RECESSED DOWNLIGHTS IN THE CANOPY SOFFIT, BY THE EC. THE GC PROVIDES CUTOUTS AND BACKING. SLOPED-CEILING ADAPTER AT THE SLOPING SOFFIT; STANDARD TRIM AT THE LEVEL SOFFIT.
54 PAINT EXISTING GWB SOFFIT, FASCIA AND COLUMNS

AGCS STATE ROAD ADMINISTRATION

110 E State Rd, West Grove, PA 19390

HSA PROJECT # :26-004

[redacted] HSA
Heckendorn Shiles Architects

PROJECT TEAM

CLIENT
Avon Grove Charter School
110 E State Rd
West Grove, PA 19390
484-667-5000


ARCHITECTURAL
Heckendorn Shiles Architects
347 East Conestoga Road
Wayne, PA 19087
610-994-3500

STRUCTURAL
Orndorf & Associates, Inc
8600 West Chester Pike, Suite 201
Upper Darby, PA 19802

MEPFP
Schiller & Hersh Associates, Inc.
636 Skippack Pike, Suite 200
Blue Bell, PA 19422
215-886-8947

NOT FOR CONSTRUCTION

KEYPLAN



LEGEND

OUT OF ARCHITECTURAL SCOPE

ISSUE HISTORY

Δ	DATE	ISSUED FOR
1	11-09-2026	BID ISSUE

SHEET TITLE

NEW CONSTRUCTION REFLECTED CEILING PLAN

DRAWING NUMBER

A110


HECKENDORN SHILES ARCHITECTS expressly reserves its common law copyright and other property rights in these plans. These are not to be reproduced, nor are they to be assigned to any third party, without first obtaining the expressed written consent of HECKENDORN SHILES ARCHITECTS

11/10/2026 3:59:10 PM

11/10/2026 3:59:11 PM
HECKENDORN SHILES ARCHITECTS expressly reserves its common law copyright and other property rights in these plans. These are not to be reproduced, nor are they to be assigned to any third party, without first obtaining the expressed written consent of HECKENDORN SHILES ARCHITECTS

SHEET NOTES

1. REFER TO A601 FOR FINISH AND ROOM SCHEDULES.
2. PAINT WALLS P-1 UNO.
3. PROVIDE WALL BASE WB-1 UNO.
4. PAINT HM DOORS AND FRAMES P-4 UNO.
5. REFER TO A5 SERIES FOR TILE TRANSITION DETAILS AND FLOOR TRANSITION DETAILS.
6. PATCH EXISTING FLOOR, WALL, BASE, AND CEILING FINISHES FOR A SEAMLESS FINISH. EXTEND SCOPE OUTSIDE OF AREA INDICATED AS REQUIRED TO ACHIEVE A DURABLE AND FINISHED LOOK AVOIDING CLEAR JOINTS AT CONSTRUCTION START / STOP POINTS. PARTIALLY REMOVE EXISTING FINISHES AS REQUIRED TO ACHIEVE THIS LOOK.
7. CENTER ALL FLOOR PATTERNS IN ROOMS AND CORRIDORS UNO.
8. EXTEND FLOORING MATERIAL INTO ALL CLOSETS, APPLIANCE BAYS AND AT OPEN COUNTERS, UNO.
9. PROVIDE FLUSH FINISH AT CHANGED IN FLOORING MATERIAL USING FLASH PATCHING OR OTHER ARCHITECT APPROVED METHOD. ALIGN TRANSITIONS TO THE CENTER OF DOORS, WHERE APPLICABLE, UNO.
10. USE MANUFACTURER'S RECOMMENDATIONS FOR ADHESIVES AT ALL SEAMS, JOINTS, AND EDGES TO ASSURE STABILITY.
11. PREPARE EXISTING FLOOR SURFACES PER MANUFACTURER'S RECOMMENDATIONS, FILL UNEVEN AREAS, AND REMOVE ALL LUMPS AND PROJECTIONS FOR A FLUSH SURFACE.
12. PAINT EXPOSED COLUMNS
13. ALL EXPOSED SURFACES AND MATERIALS TO BE FINISHED, UNO.
14. ALL EXPOSED BEAMS, ROOF DECK, DUCTWORK, CONDUIT ETC., TO BE PAINTED UNO
15. FINISH TO SLOPE AT ALL FLOOR DRAINS REFER TO SHEET AS00 FOR ADDL INFO.



1 A120 NEW CONSTRUCTION FINISH PLAN
3/16" = 1'-0"

FLOOR FINISH LEGEND

- X# — FLOOR FINISH ONLY
- X# / X# / X# — WALL FINISH / WALL BASE / FLOOR FINISH
- *NOTE: WHEN MORE THAN 3 FINISH TAGS ARE SHOWN, REFER TO ELEVATIONS AND DETAILS FOR TYPICAL LOCATIONS WITHIN THE ROOM
- X# — FINISH TO EXTENT INDICATED BY ARROWS
- T1 — TRANSITION TYPE, REFER TO DETAILS FOR ADDITIONAL INFORMATION
- RF-1 — RESILIENT FLOORING
- CPT-1 — CARPET TILE
- CPT-2 — CARPET TILE
- LVT-1 — LUXURY VINYL TILE
- VCT-1 — VINYL COMPOSITE TILE
- EXISTING VINYL COMPOSITE TILE

AGCS STATE ROAD ADMINISTRATION

110 E State Rd, West Grove, PA 19390

HSA PROJECT # :26-004

[redacted] HSA
Heckendorn Shiles Architects

PROJECT TEAM

CLIENT
Avon Grove Charter School
110 E State Rd
West Grove, PA 19390
484-667-5000


ARCHITECTURAL
Heckendorn Shiles Architects
347 East Conestoga Road
Wayne, PA 19087
610-994-3500

STRUCTURAL
Omdorf & Associates, Inc
8600 West Chester Pike, Suite 201
Upper Darby, PA 19802

MEPFP
Schiller & Hersh Associates, Inc.
636 Skippack Pike, Suite 200
Blue Bell, PA 19422
215-886-8947

NOT FOR CONSTRUCTION

KEYPLAN



LEGEND

OUT OF ARCHITECTURAL SCOPE

ISSUE HISTORY

#	DATE	ISSUED FOR
1	11-09-2026	BID ISSUE

SHEET TITLE

NEW CONSTRUCTION FINISH PLAN

DRAWING NUMBER

A120

NEW CONSTRUCTION SHEET NOTES

1. FURNITURE AND EQUIPMENT ARE FURNISHED AND INSTALLED BY OWNER (NIC) UNLESS NOTED OTHERWISE IN THE EQUIPMENT SCHEDULE. FURNITURE IS SHOWN FOR COORDINATION OF POWER, DATA AND CLEARANCES ONLY.
2. EC TO PROVIDE POWER AND DATA ROUGH-IN AT LOCATIONS SHOWN ON E201 AND E301. COORDINATE FINAL DEVICE LOCATIONS AND MOUNTING HEIGHTS WITH THE FURNITURE AND CASEWORK LAYOUT SHOWN BEFORE ROUGH-IN.
3. EC TO MAKE FINAL CONNECTION OF OWNER-FURNISHED EQUIPMENT REQUIRING HARDWIRED OR DEDICATED POWER, WHERE LISTED IN THE EQUIPMENT SCHEDULE.
4. REFER TO EQUIPMENT SCHEDULE ON A600 FOR EQ TAGS.


SHEET KEYNOTES

(XXX) = KEYNOTE TAG

46 OWNER-FURNISHED COPIER. EC TO PROVIDE DEDICATED 20A, 120V RECEPTACLE AND DATA OUTLET. CONFIRM REQUIREMENTS WITH OWNER'S VENDOR BEFORE ROUGH-IN.

47 RECEPTACLES AND DATA AT COUNTER TO BE MOUNTED ABOVE BACKSPLASH AT 42" AFF, UNO. COORDINATE WITH CASEWORK SHOP DRAWINGS.

48 SECURITY DEVICES AT DESK (VIDEO INTERCOM MASTER STATION AND EMERGENCY PANIC BUTTON) BY SECURITY VENDOR, WIRED BY EC. COORDINATE LOCATION AT OR BELOW COUNTER WITH OWNER AND CASEWORK. REFER TO E002 AND E301.



1 A130 NEW CONSTRUCTION FFE PLAN
3/16" = 1'-0"

AGCS STATE ROAD ADMINISTRATION

110 E State Rd, West Grove, PA 19390

HSA PROJECT # :26-004

[redacted] HSA
Heckendorn Shiles Architects

PROJECT TEAM

CLIENT
Avon Grove Charter School
110 E State Rd
West Grove, PA 19390
484-667-5000


ARCHITECTURAL
Heckendorn Shiles Architects
347 East Conestoga Road
Wayne, PA 19087
610-994-3500

STRUCTURAL
Omdorf & Associates, Inc
8600 West Chester Pike, Suite 201
Upper Darby, PA 19802

MEPFP
Schiller & Hersh Associates, Inc.
636 Skippack Pike, Suite 200
Blue Bell, PA 19422
215-886-8947

NOT FOR CONSTRUCTION

KEYPLAN



LEGEND

OUT OF ARCHITECTURAL SCOPE

ISSUE HISTORY

#	DATE	ISSUED FOR
1	11-09-2026	BID ISSUE

SHEET TITLE


NEW CONSTRUCTION FFE PLAN

DRAWING NUMBER


A130

HECKENDORN SHILES ARCHITECTS expressly reserves its common law copyright and other property rights in these plans. These are not to be reproduced, nor are they to be assigned to any third party, without first obtaining the expressed written consent of HECKENDORN SHILES ARCHITECTS


11/10/2026 3:59:31 PM




5 A200 ENLARGED ELEV @ CANOPY EAST WING WALL
3/8" = 1'-0"




4 A200 ENLARGED ELEVATION @ SCHOOL LETTERING
3/8" = 1'-0"



3 A200 ENLARGED ELEVATION @ BRICK FACADE
3/8" = 1'-0"



2 A200 ENLARGED METAL PANEL RETURN WALL
3/8" = 1'-0"



1 A200 NEW CONSTRUCTION SOUTH EXTERIOR ELEVATION
3/16" = 1'-0"

SHEET NOTES

1. ALL INSULATED EXTERIOR GLAZING TO RECIEVE SOLARBAN 70.
2. ROOF/PARAPET COPING AND EDGE TRIM TO MATCH WALL PANEL, UNO.
3. AS PER SPECIFICATIONS, ALL ALUMINUM STOREFRONT SYSTEMS TO BE DELEGATED DESIGN.

SHEET KEYNOTES

(XXX) = KEYNOTE TAG

01	CLEAR ANNODIZED ALUMINUM STOREFRONT SYSTEM W/ 1" INSULATED GLAZING. REFER TO ENLARGED ELEVATIONS FOR ADD1 INFO. BOD: YKK YES 45 TU
02	INFILL EXIST. PTAC OPNG W/ SOLID MASONRY (2 WYTHES BRICK + 4" CMU, V.I.F.) BRICK TOOTHED INTO EXIST. TO MATCH COURSING. COLOR MATCH TO ADJACENT BRICK
03	INFILL EXIST. PTAC OPNG W/ SOLID MASONRY (2 WYTHES BRICK + 4" CMU, V.I.F.) BRICK TOOTHED INTO EXIST. TO MATCH COURSING.
04	ALUMINUM METAL WALL PANEL SYSTEM - BOD: ZEEFF ORIGIN PREMIER FLAT PANEL 60"X24". INSTALLED WITH A 1/2 VERTICAL JOINT STAGGER. PROVIDE FORMED CORNERS AT ALL EXTERIOR CORNERS
05	PROVIDE METAL COPING TO MATCH METAL PANEL, COPING PROFILE TO BE SIMILAR TO EXISTING, EXTENDED AS REQUIRED FOR NEW WALL THICKNESS.
06	EXISTING BRICK TO REMAIN
08	ARTWORK BY OWNER VENDOR, COORD INSTALLATION AND ATTACHMENT
09	EXISTING ENTRANCE DOORS AND AUTOMATIC OPERATOR TO REMAIN. PROTECT DURING CONSTRUCTION. NEW ADA PUSHBUTTONS PER A101
10	BLACK PHENOLIC FASCIA AT CANOPY.
11	RELOCATED CARD READER AND CAMERA BY SECURITY VENDOR, WIRED BY EC. LOCATE PER E301. GC TO PROVIDE BLOCKING AND PANEL CUTOUTS.
12	BOTTOM OF METAL PANEL HELD 8" ABOVE GRADE. CLEAN EXPOSED BASE BRICK AND COAT WITH BREATHABLE WATER-REPELLENT MASONRY COLOR COATING, BOD: PROSOCO BMC II.
13	SEALANT AND BACKER ROD AT ALL METAL PANEL TERMINATIONS TO BRICK, STOREFRONT AND WINDOW FRAMES.
14	NEW ROOFTOP EQUIPMENT BEYOND. REFER TO A102 AND MECHANICAL DRAWINGS.
15	RAINWATER CONDUCTOR AND OVERFLOW OUTLET THROUGH EXISTING WALL. PROVIDE LAMBS TOUNGE FOR OVERFLOW DRAIN. PREFINISHED, COLOR TO MATCH METAL PANEL REFER TO A102 & A504.
16	EXPOSED ARCHITECTURAL CONCRETE PIER WITH 1" CHAMFER. REFER TO A402 AND STRUCTURAL DRAWINGS.
17	STEEL V-COLUMN, REFER TO STRUCTURAL DRAWINGS. FIELD PAINT, COLOR SELECTED BY ARCHITECT.
18	METAL FASCIA EDGE
19	PAINT EXISTING TRIM / PANEL TO MATCH ADJACENT EXTERIOR METAL PANEL
20	BOLLARDS SPACED 5'-0" O.C., 18" INBOUND OF CURB LINE. SEE A505 FOR DETAILS

HEICKENDORN SHILES ARCHITECTS expressly reserves its common law copyright and other property rights in these plans. These are not to be reproduced, nor are they to be assigned to any third party, without first obtaining the expressed written consent of HEICKENDORN SHILES ARCHITECTS

11/10/2026 3:59:33 PM

AGCS STATE ROAD ADMINISTRATION

110 E State Rd, West Grove, PA 19390

HSA PROJECT # :26-004

[redacted] HSA
Heckendorn Shiles Architects

PROJECT TEAM

CLIENT
Avon Grove Charter School
110 E State Rd
West Grove, PA 19390
484-667-5000

ARCHITECTURAL
Heckendorn Shiles Architects
347 East Conestoga Road
Wayne, PA 19087
610-994-3500

STRUCTURAL
Omdorf & Associates, Inc
8600 West Chester Pike, Suite 201
Upper Darby, PA 19802

MEPFP
Schiller & Hersh Associates, Inc.
636 Skippack Pike, Suite 200
Blue Bell, PA 19422
215-886-8947

NOT FOR CONSTRUCTION

LEGEND

OUT OF ARCHITECTURAL SCOPE

ISSUE HISTORY

#	DATE	ISSUED FOR
1	11-09-2026	BID ISSUE

SHEET TITLE

NEW CONSTRUCTION EXTERIOR ELEVATIONS

DRAWING NUMBER

A200

SHEET KEYNOTES

(XXX) = KEYNOTE TAG

16 NEW DEDICATED OUTDOOR AIR UNIT ON 18" HIGH ROOF CURB FURNISHED BY MC. GC TO PROVIDE ROOF OPENING AND FRAMING PER STRUCTURAL (1/S5.1, 2/S5.1), AND ROOFING AND CURB FLASHING PER 15/A506. REFER TO MECHANICAL DRAWINGS FOR UNIT, SIZE AND LOCATION PROVIDE PT BLOCKING FOR LEVELING CURBS AND RAILS. COORDINATE ROOF CRICKETS TO DIVERT WATER AROUND CURBS/SUPPORTS/EQUIPMENT AS REQUIRED. SEAL ROOF PER ROOF PENETRATION DETAILS.

17 NEW OUTDOOR HEAT RECOVERY UNIT ON EQUIPMENT RAILS PER 17/A506. SUPPORT PER STRUCTURAL DRAWINGS. REFER TO MECHANICAL DRAWINGS FOR UNIT AND LOCATION.


24 NEW CANOPY ROOF: EPDM ROOFING ON EXTERIOR SHEATHING OVER METAL DECK, SLOPED AS SHOWN. REFER TO 4/A300, 4/A402 AND STRUCTURAL DRAWINGS.

25 CANOPY ROOF EDGE: PHENOLIC PANEL FASCIA WITH FASCIA COVER AND 24 GA GALVANIZED STEEL WATERDAM PER 5/A402.


26 TIE NEW EPDM ROOFING INTO EXISTING ROOF SYSTEM PER 3/A506 AND 12/A506.

32 SLOPING, PHENOLIC PANEL SOFFIT AP-1 ON HAT CHANNEL OVER LIGHT-GAUGE FRAMING. PANEL JOINTS AS SHOWN ON THE ENLARGED RCP. COORDINATE FIXTURE CUTOUTS SO NONE LAND ON A PANEL JOINT.


56 PROVIDE TAPERED INSULATION TO DIRECT WATER TO ROOF DRAIN AND OVERFLOW DRAIN




4 CANOPY - CROSS SECTION
4 / A300 — 1/4" = 1'-0"



3 SECTOR A CROSS SECTION
3 / A300 — 1/4" = 1'-0"



2 SECTOR B CROSS SECTION
2 / A300 — 1/4" = 1'-0"



1 OVERALL LONGITUNIDAL BUILDING SECTION
1 / A300 — 1/4" = 1'-0"

11/10/2026 3:59:41 PM
HECKENDORN SHILES ARCHITECTS expressly reserves its common law copyright and other property rights in these plans. These are not to be reproduced, nor are they to be assigned to any third party, without first obtaining the expressed written consent of HECKENDORN SHILES ARCHITECTS

AGCS STATE ROAD ADMINISTRATION

110 E State Rd, West Grove, PA 19390

HSA PROJECT # :26-004

[redacted] HSA
Heckendorn Shiles Architects

PROJECT TEAM

CLIENT
Avon Grove Charter School
110 E State Rd
West Grove, PA 19390
484-667-5000

ARCHITECTURAL
Heckendorn Shiles Architects
347 East Conestoga Road
Wayne, PA 19087
610-994-3500

STRUCTURAL
Omdorf & Associates, Inc
8600 West Chester Pike, Suite 201
Upper Darby, PA 19802

MEPFP
Schiller & Hersh Associates, Inc.
636 Skippack Pike, Suite 200
Blue Bell, PA 19422
215-886-8947

NOT FOR CONSTRUCTION

LEGEND

OUT OF ARCHITECTURAL SCOPE

ISSUE HISTORY


Δ	DATE	ISSUED FOR
1	11-09-2026	BID ISSUE

SHEET TITLE


NEW CONSTRUCTION BUILDING SECTIONS

DRAWING NUMBER


A300




4 A310 WALL SECTION AT MAIN ENTRANCE
1" = 1'-0"



3 A310 WALL SECTION AT CANOPY WING WALL
1" = 1'-0"



2 A310 WALL SECTION AT RIBBON WINDOW
1" = 1'-0"



1 A310 WALL SECTION AT METAL WALL PANEL
1" = 1'-0"

AGCS STATE ROAD ADMINISTRATION

110 E State Rd, West Grove, PA 19390

HSA PROJECT # :26-004

[redacted] HSA
Heckendorn Shiles Architects

PROJECT TEAM

CLIENT
Avon Grove Charter School
110 E State Rd
West Grove, PA 19390
484-667-5000

ARCHITECTURAL
Heckendorn Shiles Architects
347 East Conestoga Road
Wayne, PA 19087
610-994-3500

STRUCTURAL
Omdorf & Associates, Inc
8600 West Chester Pike, Suite 201
Upper Darby, PA 19802

MEPFP
Schiller & Hersh Associates, Inc.
636 Skippack Pike, Suite 200
Blue Bell, PA 19422
215-886-8947

NOT FOR CONSTRUCTION

LEGEND

OUT OF ARCHITECTURAL SCOPE

ISSUE HISTORY

Δ	DATE	ISSUED FOR
1	11-09-2026	BID ISSUE

SHEET TITLE

NEW CONSTRUCTION WALL SECTIONS

DRAWING NUMBER


A310

HECKENDORN SHILES ARCHITECTS expressly reserves its common law copyright and other property rights in these plans. These are not to be reproduced, nor are they to be assigned to any third party, without first obtaining the expressed written consent of HECKENDORN SHILES ARCHITECTS


11/10/2026 3:59:46 PM



18 A400 VESTIBULE - EAST ELEVATION
3/8" = 1'-0"




13 A400 PACKAGES 124 - SOUTH ELEVATION
3/8" = 1'-0"




12 A400 WAITING 106 - NORTH ELEVATION
3/8" = 1'-0"

17 A400 COLLAB - NORTH ELEVATION
3/8" = 1'-0"


11 A400 GREETER/RECEPTION NORTH ELEVATION
3/8" = 1'-0"




10 A400 GREATER/RECEPTION - WEST ELEVATION
3/8" = 1'-0"




9 A400 GREATER/RECEPTION - EAST ELEVATION
3/8" = 1'-0"




8 A400 MAIL & COPY/PRINT - NORTH ELEVATION
3/8" = 1'-0"




7 A400 STAGING COUNTER - EAST ELEVATION
3/8" = 1'-0"




6 A400 KITCHENETTE - EAST ELEVATION
3/8" = 1'-0"




5 A400 RESTROOM 108 - EAST ELEVATION
3/8" = 1'-0"




4 A400 RESTROOM 108 - NORTH ELEVATION
3/8" = 1'-0"



3 A400 RESTROOM 108 - SOUTH ELEVATION
3/8" = 1'-0"



2 A400 RESTROOM 108 - WEST ELEVATION
3/8" = 1'-0"



1 A400 SECTOR A - ENLARGED VESTIBULE & ADMINISTRATION SUITE PLAN
1/4" = 1'-0"

AGCS STATE ROAD ADMINISTRATION

110 E State Rd, West Grove, PA 19390

HSA PROJECT # :26-004

HSA Heckendorn Shiles Architects

PROJECT TEAM

CLIENT
Avon Grove Charter School
110 E State Rd
West Grove, PA 19390
484-667-5000

ARCHITECTURAL
Heckendorn Shiles Architects
347 East Conestoga Road
Wayne, PA 19087
610-994-3500

STRUCTURAL
Omdorf & Associates, Inc
8600 West Chester Pike, Suite 201
Upper Darby, PA 19802

MEPFP
Schiller & Hersh Associates, Inc.
636 Skippack Pike, Suite 200
Blue Bell, PA 19422
215-886-8947

NOT FOR CONSTRUCTION

PLAN NORTH

LEGEND

OUT OF ARCHITECTURAL SCOPE


ISSUE HISTORY

#	DATE	ISSUED FOR
1	11-09-2026	BID ISSUE


SHEET TITLE
ENLARGED PLAN AND INT. ELEVATIONS - SECTOR A

DRAWING NUMBER
A400


11/10/2026 3:59:50 PM HECKENDORN SHILES ARCHITECTS reserves its common law copyright and other property rights in these plans. These are not to be reproduced, nor are they to be assigned to any third party, without first obtaining the expressed written consent of HECKENDORN SHILES ARCHITECTS




7 A401 NURSES STATION - WEST ELEVATION
3/8" = 1'-0"




4 A401 RESTROOM 121 - SOUTH ELEVATION
3/8" = 1'-0"




6 A401 NURSES STATION - SOUTH ELEVATION
3/8" = 1'-0"




3 A401 RESTROOM 121 - EAST ELEVATION
3/8" = 1'-0"




5 A401 RESTROOM 121 - WEST ELEVATION
3/8" = 1'-0"




2 A401 RESTROOM 121 - NORTH ELEVATION
3/8" = 1'-0"




10 A401 OFFICE 114 - WEST ELEVATION
3/8" = 1'-0"



9 A401 MOTHER'S ROOM - NORTH ELEVATION
3/8" = 1'-0"



8 A401 NURSES STATION - EAST ELEVATION
3/8" = 1'-0"



1 A401 SECTOR B - ENLARGED ADMINITRATION SUITE PLAN
1/4" = 1'-0"

AGCS STATE ROAD ADMINISTRATION

110 E State Rd, West Grove, PA 19390

HSA PROJECT # :26-004

[redacted] HSA
Heckendorn Shiles Architects

PROJECT TEAM

CLIENT
Avon Grove Charter School
110 E State Rd
West Grove, PA 19390
484-667-5000

ARCHITECTURAL
Heckendorn Shiles Architects
347 East Conestoga Road
Wayne, PA 19087
610-994-3500

STRUCTURAL
Orndorf & Associates, Inc
8600 West Chester Pike, Suite 201
Upper Darby, PA 19802

MEPFP
Schiller & Hersh Associates, Inc.
636 Skippack Pike, Suite 200
Blue Bell, PA 19422
215-886-8947

NOT FOR CONSTRUCTION

PLAN NORTH

LEGEND

OUT OF ARCHITECTURAL SCOPE

ISSUE HISTORY

#	DATE	ISSUED FOR
1	11-09-2026	BID ISSUE


SHEET TITLE

ENLARGED PLAN AND INT. ELEVATIONS - SECTOR B


DRAWING NUMBER

A401


11/10/2026 3:59:52 PM
HECKENDORN SHILES ARCHITECTS expressly reserves its common law copyright and other property rights in these plans. These are not to be reproduced, nor are they to be assigned to any third party, without first obtaining the expressed written consent of HECKENDORN SHILES ARCHITECTS




2 / A402 ENLARGED CANOPY - REFELECTED CEILING PLAN
1/4" = 1'-0"



4 / A402 ENLARGED CANOPY ELEVATION @ V COLUMN
1/4" = 1'-0"



3 / A402 ENLARGED CANOPY ELEVATION @ MAIN ENTRANCE
1/4" = 1'-0"



1 / A402 ENLARGED CANOPY PLAN
1/4" = 1'-0"

HEICKENDORN SHILES ARCHITECTS expressly reserves its common law copyright and other property rights in these plans. These are not to be reproduced, nor are they to be assigned to any third party, without first obtaining the expressed written consent of HEICKENDORN SHILES ARCHITECTS

11/10/2026 3:59:54 PM

AGCS STATE ROAD ADMINISTRATION

110 E State Rd, West Grove, PA 19390

HSA PROJECT # :26-004

[redacted] HSA
Heckendorn Shiles Architects

PROJECT TEAM

CLIENT
Avon Grove Charter School
110 E State Rd
West Grove, PA 19390
484-667-5000

ARCHITECTURAL
Heckendorn Shiles Architects
347 East Conestoga Road
Wayne, PA 19087
610-994-3500

STRUCTURAL
Omdorf & Associates, Inc
8600 West Chester Pike, Suite 201
Upper Darby, PA 19802

MEPFP
Schiller & Hersh Associates, Inc.
636 Skippack Pike, Suite 200
Blue Bell, PA 19422
215-886-8947

NOT FOR CONSTRUCTION

PLAN NORTH

LEGEND

OUT OF ARCHITECTURAL SCOPE

ISSUE HISTORY


Δ	DATE	ISSUED FOR
1	11-09-2026	BID ISSUE

SHEET TITLE


ENLARGED PLAN & EXTERIOR ELEVATIONS - CANOPY

DRAWING NUMBER


A402




5 A500 CORNER GUARD DETAIL
12" = 1'-0"




4 A500 WALL BASE DETAIL - RESILIENT COVE BASE @ RESTROOMS
6" = 1'-0"




TRANSITION AT TILE : NON-TILE



TRANSITION AT WALL TILE : WALL TILE




TRANSITION AT TILE : TILE OUTSIDE CORNERS





TRANSITION AT TILE : TILE INSIDE CORNERS

3 A500 TYPICAL TILE TRANSITION DETAILS
12" = 1'-0"




T5 RESILIENT FLOORING TO FLOOR DRAIN TRANSITION






T6 CARPET TO RESILIENT FLOOR TRANSITION


T5 RESILIENT FLOOR TRANSITION TO RESILIENT FLOOR TRANSITION






T4 RESILIENT FLOOR TO VCT TRANSITION

T3 LVT TO CARPET TRANSITION







T2 CARPET TO CARPET TRANSITION

T1 VCT TO CARPET FLOORING TRANSITION


2 A500 FLOORING TRANSITIONS
6" = 1'-0"



C2 ACT TO GWB SOFFIT FLUSH TRANSITION



C3 ACT CEILING TO GWB SOFFIT



C1 GWB SOFFIT TO EXPOSED DECK

1 A500 CEILING TRANSITIONS
3" = 1'-0"

HECKENDORN SHILES ARCHITECTS expressly reserves its common law copyright and other property rights in these plans. These are not to be reproduced, nor are they to be assigned to any third party, without first obtaining the expressed written consent of HECKENDORN SHILES ARCHITECTS

11/10/2026 3:59:55 PM

AGCS STATE ROAD ADMINISTRATION

110 E State Rd, West Grove, PA 19390

HSA PROJECT # :26-004

[redacted] HSA
Heckendorn Shiles Architects

PROJECT TEAM

CLIENT
Avon Grove Charter School
110 E State Rd
West Grove, PA 19390
484-667-5000

ARCHITECTURAL
Heckendorn Shiles Architects
347 East Conestoga Road
Wayne, PA 19087
610-994-3500

STRUCTURAL
Omdorf & Associates, Inc
8600 West Chester Pike, Suite 201
Upper Darby, PA 19802

MEPFP
Schiller & Hersh Associates, Inc.
636 Skippack Pike, Suite 200
Blue Bell, PA 19422
215-886-8947

NOT FOR CONSTRUCTION

LEGEND

OUT OF ARCHITECTURAL SCOPE

ISSUE HISTORY


Δ	DATE	ISSUED FOR
1	11-09-2026	BID ISSUE

SHEET TITLE

DETAILS - TRANSITIONS


DRAWING NUMBER

A500




PLAM BASE @ CASEWORK | RUBBER BASE @ CASEWORK | RUBBER BASE @ EXPOSED BACK OF CASEWORK | BASE @ ACCESSIBLE SINK CASEWORK

12 A501 WALL BASE DETAILS - AT CASEWORK
3" = 1'-0"




AT SOLID SURFACE EASED EDGE COUNTERTOPS | AT SOLID SURFACE WATERFALL EDGE COUNTERTOPS


11 A501 DETAIL - COUNTER AT CABINET EDGE
3" = 1'-0"




9 A501 DETAIL - COUNTER AT BACKSPLASH
3" = 1'-0"




10 A501 SECTION DETAIL - TALL CABINET
1 1/2" = 1'-0"




7 A501 SECTION DETAIL - BASE CABINET W/ADJ SHELVING AT GREETER WINDOW
1 1/2" = 1'-0"




6 A501 SECTION DETAIL - BASE CABINETRY W/ DRAWER AND ADJ SHELVING - STUDENT STATION
1 1/2" = 1'-0"




13 A501 SECTION DETAIL - UPPER CABINET W/ UNDERCABINET LIGHTING
1 1/2" = 1'-0"




3 A501 SECTION DETAIL - UPPER CABINET
1 1/2" = 1'-0"




5 A501 SECTION DETAIL - BASE CABINETRY W/ ADJ. SHELF
1 1/2" = 1'-0"



2 A501 SECTION DETAIL - BASE CABINET W/ DRAWER AND ADJ SHELVING
1 1/2" = 1'-0"



4 A501 SECTION DETAIL - BASE CABINET W/ADJ SHELVING
1 1/2" = 1'-0"



1 A501 SECTION DETAIL - BASE CABINET W/ ACCESSIBLE SINK
1 1/2" = 1'-0"

11/10/2026 3:59:55 PM
HECKENDORN SHILES ARCHITECTS reserves its common law copyright and other property rights in these plans. These are not to be reproduced, nor are they to be assigned to any third party, without first obtaining the expressed written consent of HECKENDORN SHILES ARCHITECTS

AGCS STATE ROAD ADMINISTRATION

110 E State Rd, West Grove, PA 19390

HSA PROJECT # :26-004

HSA
Heckendorn Shiles Architects

PROJECT TEAM

CLIENT
Avon Grove Charter School
110 E State Rd
West Grove, PA 19390
484-667-5000

ARCHITECTURAL
Heckendorn Shiles Architects
347 East Conestoga Road
Wayne, PA 19087
610-994-3500

STRUCTURAL
Omdorf & Associates, Inc
8600 West Chester Pike, Suite 201
Upper Darby, PA 19802

MEPFP
Schiller & Hersh Associates, Inc.
636 Skippack Pike, Suite 200
Blue Bell, PA 19422
215-886-8947

NOT FOR CONSTRUCTION

LEGEND

OUT OF ARCHITECTURAL SCOPE

ISSUE HISTORY


Δ	DATE	ISSUED FOR
1	11-09-2026	BID ISSUE

SHEET TITLE


DETAILS - CASEWORK

DRAWING NUMBER

A501




3 A502 SECTION DETAIL - WALL MOUNTED MONITOR
1 1/2" = 1'-0"




NOTE: GC TO PROVIDE BUILDING STANDARD WALL MOUNTED SHADE WITH SURFACE HEADBOX. BASIS OF DESIGN FOR ILLUSTRATIVE PURPOSES OF DESIGN INTENT IS DRAPER MANUAL FLEXSHADE NEXD SMALL HARDWARE; FABRIC: E SCREEN - CONVENTIONAL, SOLAR SHADECLOTH - FABRIC WHITE/LINEN, 5% OPEN FABRIC IN SELECT LOCATIONS COORDINATE WITH STEEL.

4 A502 DETAIL WINDOW SHADE ATTACHMENT
3" = 1'-0"



2 A502 SECTION DETAIL - COUNTERTOP SUPPORT @ GYP PARTITION
1 1/2" = 1'-0"



1 A502 SECTION DETAIL - COUNTERTOP SUPPORT @ GYP PARTITION W/ TRANSACTION WINDOW
1 1/2" = 1'-0"

AGCS STATE ROAD ADMINISTRATION

110 E State Rd, West Grove, PA 19390

HSA PROJECT # :26-004

[redacted] HSA
Heckendorn Shiles Architects

PROJECT TEAM

CLIENT
Avon Grove Charter School
110 E State Rd
West Grove, PA 19390
484-667-5000

ARCHITECTURAL
Heckendorn Shiles Architects
347 East Conestoga Road
Wayne, PA 19087
610-994-3500

STRUCTURAL
Omdorf & Associates, Inc
8600 West Chester Pike, Suite 201
Upper Darby, PA 19802

MEPFP
Schiller & Hersh Associates, Inc.
636 Skippack Pike, Suite 200
Blue Bell, PA 19422
215-886-8947

NOT FOR CONSTRUCTION

LEGEND

OUT OF ARCHITECTURAL SCOPE

ISSUE HISTORY

Δ	DATE	ISSUED FOR
1	11-09-2026	BID ISSUE


SHEET TITLE

DETAILS - GREETER DESK AND MISC. DETAILS


DRAWING NUMBER

A502


11/10/2026 3:59:56 PM HECKENDORN SHILES ARCHITECTS expressly reserves its common law copyright and other property rights in these plans. These are not to be reproduced, nor are they to be assigned to any third party, without first obtaining the expressed written consent of HECKENDORN SHILES ARCHITECTS




19 A503 DOOR DETAIL AT TILE WALL
3" = 1'-0"




14 A503 COLUMN WRAP DETAIL 05
3" = 1'-0"




18 A503 COLUMN WRAP DETAIL 09
3" = 1'-0"




13 A503 COLUMN WRAP DETAIL 04
3" = 1'-0"




17 A503 COLUMN WRAP DETAIL 08
3" = 1'-0"




12 A503 COLUMN WRAP DETAIL 03
3" = 1'-0"




16 A503 COLUMN WRAP DETAIL 07
3" = 1'-0"




11 A503 COLUMN WRAP DETAIL 02
3" = 1'-0"




15 A503 COLUMN WRAP DETAIL 06
3" = 1'-0"




10 A503 COLUMN WRAP DETAIL 01
3" = 1'-0"




20 A503 TYP HM FRAME JAMB/HEAD
3" = 1'-0"




4 A503 INT. STOREFRONT HEAD / JAMB AT CORRIDOR DTL
3" = 1'-0"




5 A503 INT. STOREFRONT DOOR JAMB AT CORRIDOR DTL
3" = 1'-0"




4 A503 INT. STOREFRONT DOOR SILL AT CORRIDOR DTL
3" = 1'-0"




3 A503 INT. STOREFRONT DOOR HEAD AT CORRIDOR DTL
3" = 1'-0"




9 A503 INT. STOREFRONT DOOR HEAD / JAMB AT 3-5/8" STUD
3" = 1'-0"




8 A503 INT. STOREFRONT DOOR JAMB AT CMU DTL
3" = 1'-0"



2 A503 INT. POCKET DOOR JAMB DETAIL
3" = 1'-0"



7 A503 INT. STOREFRONT DOOR HEAD AT CMU DTL
3" = 1'-0"



1 A503 INT. POCKET DOOR HEAD DETAIL
3" = 1'-0"

11/10/2026 3:59:57 PM HECKENDORN SHILES ARCHITECTS expressly reserves its common law copyright and other property rights in these plans. These are not to be reproduced, nor are they to be assigned to any third party, without first obtaining the expressed written consent of HECKENDORN SHILES ARCHITECTS

AGCS STATE ROAD ADMINISTRATION

110 E State Rd, West Grove, PA 19390

HSA PROJECT # :26-004

[redacted] HSA
Heckendorn Shiles Architects

PROJECT TEAM

CLIENT
Avon Grove Charter School
110 E State Rd
West Grove, PA 19390
484-667-5000

ARCHITECTURAL
Heckendorn Shiles Architects
347 East Conestoga Road
Wayne, PA 19087
610-994-3500

STRUCTURAL
Omdorf & Associates, Inc
8600 West Chester Pike, Suite 201
Upper Darby, PA 19802

MEPFP
Schiller & Hersh Associates, Inc.
636 Skippack Pike, Suite 200
Blue Bell, PA 19422
215-886-8947

NOT FOR CONSTRUCTION

LEGEND

OUT OF ARCHITECTURAL SCOPE

ISSUE HISTORY


#	DATE	ISSUED FOR
1	11-09-2026	BID ISSUE

SHEET TITLE


DETAILS - INTERIOR STOREFRONT, DOORS & COLUMN WRAP

DRAWING NUMBER


A503




18 / A504 METAL PANEL TO PHENOLIC CANOPY
3" = 1'-0"




19 / A504 METAL PANEL BRICK WALL OVERFLOW DRAIN DETAIL
3" = 1'-0"




12 / A504 METAL PANEL INSIDE CORNER TYP. DETAIL
3" = 1'-0"




8 / A504 METAL PANEL EXTERIOR WINDOW JAMB DETAIL
3" = 1'-0"




4 / A504 METAL PANEL EXTERIOR WINDOW HEAD DETAIL
3" = 1'-0"




7 / A504 EXTERIOR TRANSOM WINDOW HEAD DETAIL
3" = 1'-0"




3 / A504 METAL PANEL EXTERIOR WINDOW SILL DETAIL
3" = 1'-0"




6 / A504 EXTERIOR TRANSOM WINDOW SILL DETAIL
3" = 1'-0"




2 / A504 METAL PANEL @ TYP. JOINT DETAIL
3" = 1'-0"



15 / A504 EXT STOREFRONT DETAIL @ VERTICAL MULLION
3" = 1'-0"




11 / A504 VESTIBULE OUTSIDE CORNER DETAIL
3" = 1'-0"




17 / A504 METAL PANEL AT ROOF TIE IN DETAIL
3" = 1'-0"


14 / A504 EXT STOREFRONT DETAIL @ ACOUSTIC PARTITION
3" = 1'-0"




10 / A504 METAL PANEL OUTSIDE CORNER DETAIL
3" = 1'-0"




5 / A504 EXTERIOR WALL INFILL SECTION DETAIL
3" = 1'-0"




1 / A504 METAL PANEL EXTERIOR WALL TYP. SILL DETAIL
3" = 1'-0"



16 / A504 METAL PANEL TO PHENOLIC SOFFIT DETAIL
3" = 1'-0"



13 / A504 METAL PANEL VERTICAL JOINT TYP. DETAIL
3" = 1'-0"



9 / A504 EXTERIOR WINDOW INFILL DETAIL
3" = 1'-0"

AGCS STATE ROAD ADMINISTRATION

110 E State Rd, West Grove, PA 19390

HSA PROJECT # :26-004

HSA Heckendorn Shiles Architects

PROJECT TEAM

CLIENT
Avon Grove Charter School
110 E State Rd
West Grove, PA 19390
484-667-5000

ARCHITECTURAL
Heckendorn Shiles Architects
347 East Conestoga Road
Wayne, PA 19087
610-994-3500

STRUCTURAL
Omdorf & Associates, Inc
8600 West Chester Pike, Suite 201
Upper Darby, PA 19802

MEPFP
Schiller & Hersh Associates, Inc.
636 Skippack Pike, Suite 200
Blue Bell, PA 19422
215-886-8947

NOT FOR CONSTRUCTION

LEGEND

OUT OF ARCHITECTURAL SCOPE

ISSUE HISTORY

Δ	DATE	ISSUED FOR
1	11-09-2026	BID ISSUE

SHEET TITLE


DETAILS - EXTERIOR WALL & WINDOW

DRAWING NUMBER


A504

HECKENDORN SHILES ARCHITECTS expressly reserves its common law copyright and other property rights in these plans. These are not to be reproduced, nor are they to be assigned to any third party, without first obtaining the expressed written consent of HECKENDORN SHILES ARCHITECTS


11/10/2026 3:59:58 PM




6 A505 CONCRETE SLAB DETAIL AT EXISTING STAIR
3" = 1'-0"




8 A505 BOLLARD DETAIL
1" = 1'-0"




5 A505 CONCRETE SLAB EDGE DETAIL
3" = 1'-0"




7 A505 BOLLARD CAULK & GROUT DETAILS
3" = 1'-0"




4 A505 CONCRETE SLAB EDGE DETAIL AT EXISTING SIDEWALK
3" = 1'-0"



3 A505 METAL PANEL TO PHENOLIC AT CANOPY WING WALL
3" = 1'-0"



2 A505 LATERAL ROOF EDGE DETAIL @ CANOPY
3" = 1'-0"



1 A505 LEADING ROOF EDGE DETAIL @ CANOPY
3" = 1'-0"

AGCS STATE ROAD ADMINISTRATION

110 E State Rd, West Grove, PA 19390

HSA PROJECT # :26-004

[redacted] HSA
Heckendorn Shiles Architects

PROJECT TEAM

CLIENT
Avon Grove Charter School
110 E State Rd
West Grove, PA 19390
484-667-5000

ARCHITECTURAL
Heckendorn Shiles Architects
347 East Conestoga Road
Wayne, PA 19087
610-994-3500

STRUCTURAL
Omdorf & Associates, Inc
8600 West Chester Pike, Suite 201
Upper Darby, PA 19802

MEPFP
Schiller & Hersh Associates, Inc.
636 Skippack Pike, Suite 200
Blue Bell, PA 19422
215-886-8947

NOT FOR CONSTRUCTION

LEGEND

OUT OF ARCHITECTURAL SCOPE

ISSUE HISTORY

Δ	DATE	ISSUED FOR
1	11-09-2026	BID ISSUE

SHEET TITLE


DETAILS - EXTERIOR WALL & SITE

DRAWING NUMBER


A505

HECKENDORN SHILES ARCHITECTS reserves its common law copyright and other property rights in these plans. These are not to be reproduced, nor are they to be assigned to any third party, without first obtaining the expressed written consent of HECKENDORN SHILES ARCHITECTS


11/10/2026 3:59:59 PM




14 A506 PIPE VENT FLASHING DETAIL
3/4" = 1'-0"




9 A506 SECTION DETAIL - ROOF DRAIN
1 1/2" = 1'-0"



4 A506 SMALL PIPE AND TUBE PENETRATION
3" = 1'-0"




13 A506 PIPING PENETRATION
3/4" = 1'-0"




NOTES:
1. HOLE IN MEMBRANE SHOULD EXTEND A MIN. OF 1/2" BEYOND CLAMPING RING AND SHOULD NOT BE SMALLER THAN THE DIAMETER OF THE LEADER PIPE
2. FIRESTONE WATERBLOCK MIN. OF 1/2 OF 10 OZ TUBE PER 4" DRAIN. USE ADD/ WATERBLOCK FOR LARGER DRAINS
3. IF SEAM EDGE IS WITHIN 9" OF DRAIN COMPRESSION RING, EPDM TARGET PATCH REQ'D. IF SEAM EDGE IS WITHIN 9"-18" OF DRAIN COMPRESION RING, INSTALL A LAYER OF FLASHING CENTERED OVER SEAM EDGE. FLASHING MUST EXTEND 3" MIN. BEYOND EDGE OF SUMP.


8 A506 ROOF DETAIL - OVERFLOW DRAIN
3" = 1'-0"




3 A506 ROOF DETAIL - TIE-IN EPDM SYSTEM TO EXISTING EPDM SYSTEM
6" = 1'-0"



12 A506 ROOF DETAIL - TYPICAL BASE TIE IN
3" = 1'-0"




7 A506 ROOF DRAIN WITH OVERFLOW
3/4" = 1'-0"




NOTES:
1. WOOD NAILERS MUST BE INSTALLED WITH SUITABLE FASTENERS TO MEET APPLICABLE BUILDING CODES (200 LBS PER LINEAR FOOT MIN IN ANY GIVEN DIRECTION)
2. ALL SHEET METAL IS TO BE INSTALLED PER SMACNA GUIDELINES
3. FLASHING LAPS MUST BE OFFSET FROM FIELD LAPS BY A MINIMUM OF 12".
4. METAL COPING BY ROOFING MANUFACTURER.
5. FASTEN COPING CLEAT AS PER MANUFACTURER INSTRUCTIONS.

2 A506 ROOF DETAIL - COPING DETAIL
6" = 1'-0"




16 A506 ROOF DETAIL - BASE FLASHING AT WRB WALL
3" = 1'-0"




NOTES:
1) ALUMINUM TAPE IS REQUIRED IF EXISTING PENETRATION IS CONTAMINATED.
2) VAPOR BARRIER SHALL BE SEALED AT EDGES.


11 A506 SEC DTL @ VENT STACK FLASHING
1 1/2" = 1'-0"




6 A506 ROOFTOP EQUIPMENT RAIL DETAIL
1 1/2" = 1'-0"




EDGE DETAIL TYPICAL NOTES:
1. WOOD NAILERS MUST BE INSTALLED WITH SUITABLE FASTENERS TO MEET APPLICABLE BUILDING CODES (200 LBS PER LINEAR FOOT MIN IN ANY GIVEN DIRECTION)
2. ALL SHEET METAL IS TO BE INSTALLED PER SMACNA GUIDELINES
3. FLASHING LAPS MUST BE OFFSET FROM FIELD LAPS BY A MINIMUM OF 12".
4. FASTEN COPING CLEATS AS PER MANUFACTURER INSTRUCTIONS.



1 A506 PARAPET DETAIL @ METAL PANEL
3" = 1'-0"



5 A506 ROOF DETAIL - INSIDE CORNER W SEPARATE WALL FLASHING
6" = 1'-0"



15 A506 MECHANICAL UNIT - CURB FLASHING
1 1/2" = 1'-0"

NOTES:
1. BOTH SURFACES MUST BE CLEANED W/ EPDM TAPE PRIMER/WASH. THE PRIMER/WASH MUST BE COMPLETELY DRY & TACK FREE BEFORE LAP CEMENT APPLICATION

10 A506 ROOF DETAIL - FLASHING LAP SPLICE DETAIL
1 1/2" = 1'-0"

HECKENDORN SHILES ARCHITECTS expressly reserves its common law copyright and other property rights in these plans. These are not to be reproduced, nor are they to be assigned to any third party, without first obtaining the expressed written consent of HECKENDORN SHILES ARCHITECTS

11/10/2026 4:00:00 PM

AGCS STATE ROAD ADMINISTRATION

110 E State Rd, West Grove, PA 19390

HSA PROJECT # :26-004

HSA
Heckendorn Shiles Architects

PROJECT TEAM

CLIENT
Avon Grove Charter School
110 E State Rd
West Grove, PA 19390
484-667-5000

ARCHITECTURAL
Heckendorn Shiles Architects
347 East Conestoga Road
Wayne, PA 19087
610-994-3500

STRUCTURAL
Omdorf & Associates, Inc
8600 West Chester Pike, Suite 201
Upper Darby, PA 19802

MEPFP
Schiller & Hersh Associates, Inc.
636 Skippack Pike, Suite 200
Blue Bell, PA 19422
215-886-8947

NOT FOR CONSTRUCTION


LEGEND
OUT OF ARCHITECTURAL SCOPE

ISSUE HISTORY

Δ	DATE	ISSUED FOR
1	11-09-2026	BID ISSUE

SHEET TITLE
DETAILS - ROOF

DRAWING NUMBER
A506



1 / A600 PARTITION NON RATED HEAD DETAIL


1 1/2" = 1'-0"

PARTITION SCHEDULE


WALL TYPE	LOAD BEARING	COMBUSTABILITY	STUD	STUD SIZE	STUD THICKNESS / GAUGE	STUD SPACING	GWB THICKNESS	SAFB	PARTITION THICKNESS	REMARKS
A3D	NO	NON COMBUSTIBLE	CHANNEL	3 5/8"	.035/20	16" O.C.	5/8"		4 7/8"	
A3DS	NO	NON COMBUSTIBLE	CHANNEL	3 5/8"	.035/20	16" O.C.	5/8"	3 1/2"	4 7/8"	
A6A	NO	NON COMBUSTIBLE	CHANNEL	6"	.035/20	16" O.C.	5/8"		7 1/4"	
A6BS	NO	NON COMBUSTIBLE	CHANNEL	6"	.035/20	16" O.C.	5/8"	6"	7 1/4"	
A6DS	NO	NON COMBUSTIBLE	CHANNEL	6"	.035/20	16" O.C.	5/8"	6"	<varies>	
B1B	NO	NON COMBUSTIBLE	CHANNEL	7/8"	.035/20	16" O.C.	5/8"		1 1/2"	
B2	NO	NON COMBUSTIBLE	CHANNEL	3 5/8"	.035/20	16" O.C.	5/8"	3 5/8"	4 3/4"	
B2D	NO	NON COMBUSTIBLE	CHANNEL	2 1/2"	.035/20	16" O.C.	5/8"		3 1/8"	
B3D	NO	NON COMBUSTIBLE	CHANNEL	3 5/8"	.035/20	16" O.C.	5/8"		4 1/4"	
B3DS	NO	NON COMBUSTIBLE	CHANNEL	3 5/8"	.035/20	16" O.C.	5/8"	3 1/2"	4 1/4"	
B6A	NO	NON COMBUSTIBLE	CHANNEL	6"	.035/20	16" O.C.	5/8"		6 5/8"	
B6DS	NO	NON COMBUSTIBLE	CHANNEL	6"	.035/20	16" O.C.	5/8"	6"	7 1/4"	
C2	NO	NON COMBUSTIBLE	CHANNEL	6"	.035/20	16" O.C.	5/8"		7 1/4"	PARTITION TO BE CLAD IN WP-1 ON ALL SIDES
X3DS	NO	NON COMBUSTIBLE	CHANNEL	3 5/8"	.035/20	16" O.C.	5/8"	3 1/2"	9 1/2"	

PARTITION TYPES


PARTITION TYPE A3D




PARTITION TYPE A3DS




PARTITION TYPE A6A




PARTITION TYPE A6BS




PARTITION TYPE A6DS




PARTITION TYPE B1B




PARTITION TYPE B2




PARTITION TYPE B2D




PARTITION TYPE B3D




PARTITION TYPE B3DS



PARTITION TYPE B6DS



PARTITION TYPE X3DS



NOTE: AVOID BRACING OF STUD ROWS. IF REQUIRED USE LATERAL BRACING IN ACCORDANCE W/ UL U493.

SCHEDULE NOTES

1. REFER TO PARTITION TYPES FOR HEIGHT, # OF GWB LAYERS, AND BRACING NOTES
2. GWB ON ALL PARTITIONS TO BE IMPACT-RESISTANT GWB, UNO.
3. PROVIDE GWB CONTROL JOINT EVERY 30' MIN. O.C. OR EVERY 300SF
4. PROVIDE DEFLECTION TRACK FOR THE TOP RUNNER OF STEEL-FRAMED PARTITIONS THAT ABUT THE UNDERSIDE OF STRUCTURE. CONFIRM REQUIREMENTS FOR DEFLECTION W/ PROJECT STRUCTURAL ENGINEER. REFER TO SPECIFICATIONS FOR ADDITIONAL INFORMATION.
5. PROVIDE ACOUSTIC SEALANT TOP AND BOTTOM OF ALL PARTITIONS AND AT ALL PENETRATIONS, U.N.O.
6. PROVIDE FIRE RATED CONCEALED BLOCKING IN ALL PARTITIONS INCLUDING, BUT NOT LIMITED TO, OPEN AND CLOSED SHELVING, COAT RODS, SHELVES, CABINETRY, COUNTERS, DOOR FRAMES AND HEADER.
7. COORDINATE AND PROVIDE IN-WALL BLOCKING AS REQUIRED FOR EQUIPMENT ATTACHMENT.
8. COORDINATE PARTITION FRAMING W/ ALL RECESSED AND SEMI-RECESSED EQUIPMENT AND/OR FURNISHINGS
9. GYPSUM WALL BOARD ON ALL PARTITIONS IN RESTROOMS, BATHROOMS, AND SHOWER ROOMS TO BE MOISTURE AND MOLD RESISTANT, UNO.
10. GYPSUM WALL BOARD AT ALL LOCATIONS TO RECEIVE TILE FINISH TO BE 5/8" WATER RESISTANT TILE BACKING PANELS, UNO
11. REFER TO PARTITION HEAD DETAILS FOR REQUIREMTNS AT RATED AND ACOUSTIC PARTITIONS.

AGCS STATE ROAD ADMINISTRATION

110 E State Rd, West Grove, PA 19390

HSA PROJECT # :26-004

HSA Heckendorn Shiles Architects

PROJECT TEAM

CLIENT
Avon Grove Charter School
110 E State Rd
West Grove, PA 19390
484-667-5000

ARCHITECTURAL
Heckendorn Shiles Architects
347 East Conestoga Road
Wayne, PA 19087
610-994-3500

STRUCTURAL
Omdorf & Associates, Inc
8600 West Chester Pike, Suite 201
Upper Darby, PA 19802

MEPFP
Schiller & Hersh Associates, Inc.
636 Skippack Pike, Suite 200
Blue Bell, PA 19422
215-886-8947

NOT FOR CONSTRUCTION

ISSUE HISTORY

Δ	DATE	ISSUED FOR
1	11-09-2026	BID ISSUE

SHEET TITLE


PARTITION SCHEDULE & DETAILS

DRAWING NUMBER

A600

11/10/2026 4:00:01 PM HECKENDORN SHILES ARCHITECTS expressly reserves its common law copyright and other property rights in these plans. These are not to be reproduced, nor are they to be assigned to any third party, without first obtaining the expressed written consent of HECKENDORN SHILES ARCHITECTS

DOOR TYPES



TYPE A1
SINGLE DOOR
FLUSH SCW W/
WOOD VENEER
FACE - WHITE
MAPLE, PLAIN
SLICED

TYPE B1
SINGLE DOOR
W/ HALF VISION PANEL
SCW W/WOOD
VENEER FACE - WHITE
MAPLE, PLAIN SLICED


TYPE C1
SINGLE ALUM DOOR
W/ FULL VISION GLASS
CLEAR ANODIZED
MEDIUM STILE

TYPE D1
SINGLE ALUM DOOR
W/ FULL VISION GLASS
CLEAR ANODIZED
NARROW STILE

TYPE E1
SINGLE DOOR
FLUSH HM - PTD

TYPE F1
SINGLE DOOR
FLUSH SCW W/
WOOD VENEER
FACE - WHITE
MAPLE, PLAIN
SLICED

FRAME TYPES



FRAME TYPE A
HM FRAME SINGLE
DOOR

FRAME TYPE B
HM FRAME FOR
SINGLE DOOR W/
SIDELIGHT


FRAME TYPE C
ALUM. FRAME
SINGLE DOOR
(INTEGRATED INTO
CONTINUOUS
STOREFRONT)

FRAME TYPE D
HEAVY DUTY POCKET
FRAME (COORDINATE
WITH PARTITION
CONSTRUCTION


INTERIOR STOREFRONT SCHEDULE

TAG	HEIGHT	WIDTH	TYPE	MATERIAL	REMARKS
S1	7' - 2"	8' - 8 1/2"	INTERIOR STOREFRONT - DOUBLE HALF LIGHT	CLR ANNONDIZED ALUMINUM	
S2	8' - 0"	5' - 6 1/32"	INTERIOR STOREFRONT - SINGLE HALF LIGHT	CLR ANNONDIZED ALUMINUM	
S3	8' - 0"	6' - 6 7/8"	INTERIOR STOREFRONT - SINGLE HALF LIGHT	CLR ANNONDIZED ALUMINUM	
S4	8' - 0"	5' - 6 1/32"	INTERIOR STOREFRONT - FULL HEIGHT LIGHT	CLR ANNONDIZED ALUMINUM	
S5	8' - 0"	9' - 10"	INTERIOR STOREFRONT - DOUBLE LIGHT	CLR ANNONDIZED ALUMINUM	


NOTES:
1. INTERIOR STOREFRONT BOD: YKK INTERIOR STOREFRONT YES 45 FI - 1" IGU AS SPECIFIED
2. ALL INTERIOR STOREFRONT TO RECEIVE TEMPERED GLAZING U.N.O.




TYPE S1
FIXED STOREFRONT




TYPE S2
FIXED STOREFRONT



TYPE S3
FIXED STOREFRONT



TYPE S4
FIXED STOREFRONT




TYPE S5
FIXED STOREFRONT

EXTERIOR STOREFRONT SCHEDULE

TAG	SIZE HEIGHT	SIZE WIDTH	TYPE	MATERIAL	REMARKS
W1	5' - 4"	2' - 0"	EXTERIOR STOREFRONT - INFILL TYPE 1	CLR ANNONDIZED ALUMINUM	
W2	5' - 4"	3' - 3 3/4"	EXTERIOR STOREFRONT - INFILL TYPE 2	CLR ANNONDIZED ALUMINUM	
W3	4' - 0"	24' - 8"	EXTERIOR STOREFRONT - CLERESTORY	CLR ANNONDIZED ALUMINUM	


NOTES:
1. INTERIOR STOREFRONT BOD: YKK INTERIOR STOREFRONT YES 45 FI - 1" IGU AS SPECIFIED
2. ALL INTERIOR STOREFRONT TO RECEIVE TEMPERED GLAZING U.N.O.



TYPE W1
FIXED STOREFRONT



TYPE W2
FIXED STOREFRONT



TYPE W3
FIXED STOREFRONT

NOTES:
1. INTERIOR STOREFRONT BOD: YKK INTERIOR STOREFRONT YES 45 FI - 1" IGU AS SPECIFIED
2. ALL INTERIOR STOREFRONT TO RECEIVE TEMPERED GLAZING U.N.O.
3. WHERE SPANDRAL GLS-5 IS VISIBLE ON INTERIOR, INTERIOR FACE OF GLAZING TO BE FINISHED TO MATCH ADJACENT WALL COLOR

GLAZING SCHEDULE

TAG	DESCRIPTION	REMARKS
GLS-1	INTERIOR INSULATED GLAZING UNIT	CLEAR INSULATING GLASS
GLS-2	INTERIOR INSULATED SECURITY GLAZING UNIT	CLEAR INSULATING GLASS, SCHOOL GUARD GLAZING
GLS-3	INTERIOR GLAZING	CLEAR GLASS
GLS-4	EXTERIOR INSULATED SECURITY GLAZING UNIT	LOW-E COATED CLEAR INSULATING GLASS CLEAR, SCHOOL GUARD GLAZING, SOLARBAN 70
GLS-5	EXTERIOR INSULATED SECURITY GLAZING UNIT - SPANDRAL	LOW-E COATED CLEAR INSULATING SPANDRAL GLASS, SOLARBAN 70

NOTES:
1. REFER TO STOREFRONT TYPES FOR LOCATIONS
2. REFER TO SPECIFICATIONS FOR ADDITIONAL INFORMATION
3. ALL EXTERIOR INSULATED GLAZING TO BE SOLARBAN 70
4. ALL GLAZING TO BE TEMPERED IN LOCATIONS THAT SILL HEIGHT IS LESS THAN 36" AFF
5. ALL GLAZING IN DOORS AND ADJACENT SIDELIGHTS TO BE TEMPERED
6. ALL GLAZING WITHIN 0 - 36" AFF TO BE TEMPERED GLAZING

FINISH SCHEDULE

TAG	MANUFACTURER	STYLE	COLOR	REMARKS
ACOUSTIC CEILING TILE				
ACT-1	ARMSTRONG	ULTIMA TEGULAR #1042	WHITE	2'X2', SILHOUETTE XL 9/16" BOLT SLOT - 1/4" REVEAL, CEILING TILE, GENERAL CEILING TILE
ACT-2	ARMSTRONG	OPTIMA LAY-IN SQUARE #3160	WHITE	4'X4' CEILING TILE, PRELUDE XL 15/16" CEILING GRID, AT CORRIDOR
ARCHITECTURAL PHENOLIC PANELS				
AP-1	ABET LAMIMATI	MERCER CHERRY	-	EXTERIOR CANOPY AND SOFFIT. REFER TO RCP AND ELEVATIONS FOR ADDL INFORMATION. FASTENERS FINISHED TO MATCH PANEL
CARPET TILE				
CPT-1	TARKETT	11251 FORMATION	SIDERITE 58208	24"X24" CARPET TILE AT ADMIN SUITE & PRIVATE OFFICES; ASHLAR INSTALLATION; CONTACT: MELISSA CARNIVAL MELISSA.CARNIVAL@TARKETT.COM
CPT-2	TARKETT	11129 TEXTUREMAP	TOMORROWLAND 42801	24X24 CARPET TILE AT CONFERENCE ROOM; ASHLAR INSTALLATION
CPT-3	MANNINGTON COMMERCIAL	INERTIA	SLIDE 34368	18"X36" WALKOFF TILE INSTALLED ASHLAR AT VESTIBULES
CERAMIC WALL TILE				
CT-1	NEMO	METRO NEUTRAL I	BONE	4"X12" SINGLE USER RESTROOM GENERAL WALL TILE, RUNNING BOND INSTALLATION, REFER TO ELEVATIONS FOR PATTERN; 1/16" MAPEI GROUT 49 LIGHT ALMOND
CT-2	NEMO	METRO BOLD II	CLOUD	4"X12" SINGLE USER RESTROOM GENERAL WALL TILE, RUNNING BOND INSTALLATION, REFER TO ELEVATIONS FOR PATTERN; 1/16" MAPEI GROUT 49 LIGHT ALMOND
CORNER GUARD				
CG-1	INPRO	160F CORNER GUARD		8' H AT ALL GWB CORNERS, INSTALL CORNER GAURDS 6' AFF FREFER TO CORNER GAURD DETAIL - FOR ADDL INFO
LUXURY VINYL TILE				
LVT-1	PATCRAFT	1847V TIMBER GROVE III	00142 SOUTHERN SKY - V2	20 MIL, 5.96" X 48" PLANKS, FLOOR FINISH AT KITCHENETTE
PAINT				
P-1	BENJAMIN MOORE	OC-69	WHITE OPULENCE	GENERAL WALL PAINT
P-2	BENJAMIN MOORE	CSP-255	WICKER BASKET	ACCENT PAINT
P-3	BENJAMIN MOORE	2123-10	MEDITERRANEAN TEAL	ACCENT PAINT
PLASTIC LAMINATE				
PL-1	FORMICA	COLORCORE2	FOLKSTONE 927C-58	PLASTIC LAMINATE AT CASEWORK IN ADMIN
RESILIENT FLOORING				
RF-1	ALTRO FLOORING	ALTRO AQUARIUS	HIPPO AQ12013	FLOORING WITH INTEGRATED 6" WALL BASE AT NURSES STATION AND ADJACENT SPACES
SOLID SURFACE				
SS-1	WILSONART	-	CHILLED EARTH 9228SS	GENERAL COUTERTOP
SS-2	FORMICA	EVERFORM	748 WHITE RENEW	ADMIN STATION
VINYL COMPOSITE TILE				
VCT-1	TARKETT	VCT II	598 DEEP WATER	12" X 12"X 1/8"
WALL BASE				
WB-1	TARKETT	JOHNSONITE BASEWORKS THERMOSET	20 CHARCOAL WG	4" COVE GENERAL WALL BASE
WB-2	TARKETT	JOHNSONITE BASEWORKS THERMOSET	TA1 TANNERY WB	4" COVE GENERAL WALL BASE
WALLCOVERING				
WC-1	MOMENTUM	MADE TO MATCH	LAVA	ACCENT WALLCOVERING AT MOTHER'S ROOM

ROOM FINISH SCHEDULE

ROOM NUMBER	ROOM NAME	WALL BASE	WALLS N	WALLS E	WALLS S	WALLS W	FLOOR	REMARKS
100	VESTIBULE							
100	CORRIDOR							
101	GREETER / RECEPTION	WB-1	P-1	P-2	P-1	P-1	CPT-2	PL-1 & SS-1 AT CASEWORK REFER TO PLANS AND ELEVATIONS FOR ADDL INFO
102	CORRIDOR	WB-1	P-1	P-1	P-1	P-1	CPT-1 / CPT-2	REFER TO FINISH PLANS FOR ADDL INFO
103	OFFICE	WB-1	P-2	P-1	P-1	P-1	CPT-1	REFER TO FINISH PLANS FOR ADDL INFO
104	OFFICE	WB-1	P-2	P-1	P-1	P-1	CPT-1	REFER TO FINISH PLANS FOR ADDL INFO
105	COLLAB.	WB-1	P-3	P-1	P-1	P-1	CPT-1	REFER TO FINISH PLANS FOR ADDL INFO
106	WAITING	WB-1	P-1	P-1	P-1	P-2	CPT-2	REFER TO FINISH PLANS FOR ADDL INFO
107	ADMIN	WB-1	P-1	P-1	P-1	P-2	CPT-2	PL-1 & SS-2 AT CASEWORK REFER TO PLANS AND ELEVATIONS FOR ADDL INFO
108	RR	RF-1	CT-1 / CT-2	CT-1 / CT-2	CT-1 / CT-2	CT-1 / CT-2	RF-1	REFER TO FINISH PLANS FOR ADDL INFO
109	MAIL	WB-1	P-3	P-1	P-1	P-1	CPT-2	PL-1 & SS-1 AT CASEWORK REFER TO PLANS AND ELEVATIONS FOR ADDL INFO
110	COPY / PRINT	WB-1	P-3	P-1	P-1	P-1	CPT-2	PL-1 & SS-1 AT CASEWORK REFER TO PLANS AND ELEVATIONS FOR ADDL INFO
111	KITCHENETTE	WB-2	P-1	P-3	P-1	P-1	LVT-1	REFER TO FINISH PLANS FOR ADDL INFO
112	STORAGE	WB-1	P-1	P-1	P-1	P-1	CPT-1	REFER TO FINISH PLANS FOR ADDL INFO
113	UTILITY	WB-1	P-1	P-1	P-1	P-1	CPT-1	REFER TO FINISH PLANS FOR ADDL INFO
114	OFFICE	WB-1	P-1	P-2	P-1	P-1	CPT-1	REFER TO FINISH PLANS FOR ADDL INFO
115	MOTHER'S ROOM	WB-1	P-1 / WC-1	P-1	P-	P-1	CPT-1	WC-1, PL-1 & SS-1 AT CASEWORK REFER TO PLANS AND ELEVATIONS FOR ADDL INFO
116	RECEPTION	WB-1	P-1	P-1	P-1	P-3	CPT-1	REFER TO FINISH PLANS FOR ADDL INFO
117	STORAGE	WB-1	P-1	P-1	P-1		CPT-1	REFER TO FINISH PLANS FOR ADDL INFO
118	OFFICE	WB-1	P-1	P-1	P-2	P-1	CPT-1	REFER TO FINISH PLANS FOR ADDL INFO
119	OFFICE	WB-1	P-1	P-2	P-1	P-1	CPT-1	REFER TO FINISH PLANS FOR ADDL INFO
120	NURSES STATION	WB-1	P-1	P-1	P-1	P-3	RF-1	PL-1 & SS-1 AT CASEWORK REFER TO PLANS AND ELEVATIONS FOR ADDL INFO
121	RR	RF-1	CT-1 / CT-2	CT-1 / CT-2	CT-1 / CT-2	CT-1 / CT-2	RF-1	REFER TO FINISH PLANS FOR ADDL INFO
122	COATS	WB-1	P-1	P-1	P-1	P-1	RF-1	REFER TO FINISH PLANS FOR ADDL INFO
123	STORAGE	WB-1	P-1	P-1	P-1	P-1	VCT-1	REFER TO FINISH PLANS FOR ADDL INFO
124	PACKAGES	WB-1	P-1	P-1	P-1	P-1	VCT-1	REFER TO FINISH PLANS FOR ADDL INFO
125	LOST & FOUND	WB-1	P-1	P-1	P-1	P-1	VCT-1	REFER TO FINISH PLANS FOR ADDL INFO

SPECIALTY EQUIPMENT SCHEDULE

TAG	ITEM	SPECIFICATION	WIDTH	HEIGHT	DEPTH	PROVIDED BY	INSTALLED BY	REMARKS
EQ-01	FLOOR ACCESS HATCH	Bilco				GC	GC	
EQ-02	COMBINATION FREEZER / REFRIGERATOR	GE APPLIANCES				OWNER	OWNER	PROVIDE WATER HOOKUP TO FREEZER FOR ICE MAKER
EQ-03	MICROWAVE	GE, JES1145SH				OWNER	OWNER	
EQ-04	UNDERCOUNTER REFRIGERATOR	SUMMIT APPLIANCE AL55				OWNER	OWNER	
EQ-05	COPIER	LANIER IM C6000				OWNER	OWNER	
EQ-06	65" DISPLAY	BY OWNER / VENDOR				OWNER	OWNER	
EQ-07	DESKTOP COPIER					OWNER	OWNER	
EQ-08	PAPER SHREDDER					OWNER	OWNER	
EQ-09	MONITOR					OWNER	OWNER	
EQ-10	STEEL SHELVING					OWNER	GC	
EQ-11	MAIL SORTER	SOUTHWEST SOLUTIONS GROUP FSM3612765				OWNER	OWNER	
EQ-12	DRY ERASE BOARD					OWNER	OWNER	
EQ-13	AED DEFIBRILLATOR CABINET					GC	GC	CABINET PROVIDED AND INSTALLED BY GC, AED UNIT FURNISHED AND INSTALLED BY OWNER

GC TO PROVIDE BLOCKING BEHIND WALL SURFACE TO SUPPORT THE ATTACHMENT OF ALL WALL MOUNTED FIXTURES, ACCESSORIES AND EQUIPMENT

DOOR AND FRAME SCHEDULE

DOOR NUMBER	DOOR TYPE	DOOR FINISH	DOOR SIZE WIDTH	DOOR SIZE HEIGHT	FRAME TYPE	FRAME FINISH	FRAME HEAD DETAIL	FRAME JAMB DETAIL	REMARKS
101A	C1	ALUM CLR	3' - 0"	7' - 10"	C	CLR ANNODIZED	3/A503	5/A503	PROVIDE GLS-2 IN DOOR AND SIDELIGHT, ELECTRONIC SECURITY HARDWARE W/ CARD READER
101B	D1	ALUM CLR	3' - 4"	4' - 0"					SLIDER - SIZE OF DOOR TO ALIGN TO OUTSIDE DIM OF FRAME. SLIDER ASSA ABLOY PACER SLIDING DOOR, PROVIDE GLS-2. SURFACE MOUNTED TO FACE OF PARTITION
102A	A1	STD	3' - 0"	7' - 0"	D	PTD HM	1/A503	2/A503	HEAVY DUTY POCKET DOOR FRAME HANGING KIT, BASIS OF DESIGN KARPEN STEEL WELDED METAL POCKET FRAME
102B	A1	STD	3' - 0"	7' - 0"	D	PTD HM	1/A503	2/A503	HEAVY DUTY POCKET DOOR FRAME HANGING KIT, BASIS OF DESIGN KARPEN STEEL WELDED METAL POCKET FRAME
103	B1		3' - 0"	7' - 0"	C		9/A503	9/A503	PROVIDE GLS-1 IN DOOR AND SIDELIGHTS
104	B1	STD	3' - 0"	7' - 0"	C	CLR ANNODIZED	9/A503	9/A503	PROVIDE GLS-1 IN DOOR AND SIDELIGHTS
106	C1	ALUM CLR	3' - 0"	7' - 10"	C	CLR ANNODIZED	3/A503	5/A503	PROVIDE GLS-2 IN DOOR AND SIDELIGHT, ELECTRONIC SECURITY HARDWARE W/ CARD READER
108	A1	STD	3' - 0"	7' - 0"	A	PTD HM	19/A503	19/A503	COORDINATE FRAME WITH TILE INSTALLATION
112	A1	STD	3' - 0"	7' - 0"	A	PTD HM			
113	A1	STD	3' - 0"	7' - 0"	A	PTD HM			
114	B1	STD	3' - 0"	7' - 0"	A	PTD HM			PROVIDE GLS-1 IN DOOR
115	A1	STD	3' - 0"	7' - 0"	A	PTD HM			
116	C1	ALUM CLR	3' - 0"	7' - 10"	C	CLR ANNODIZED	3/A503	5/A503	PROVIDE GLS-2 IN DOOR AND SIDELIGHT, ELECTRONIC SECURITY HARDWARE W/ CARD READER
117	A1	STD	3' - 0"	7' - 0"	A	PTD HM			
118	B1	STD	3' - 0"	7' - 0"	B	PTD HM			PROVIDE GLS-1 IN DOOR AND SIDELIGHTS
119	B1	STD	3' - 0"	7' - 0"	B	PTD HM			PROVIDE GLS-1 IN DOOR AND SIDELIGHTS
120	C1	ALUM	3' - 0"	7' - 10"	C	CLR ANNODIZED	5/A503	6/A503	PROVIDE GLS-2 IN DOOR AND SIDELIGHT, ELECTRONIC SECURITY HARDWARE W/ CARD READER
121	A1	STD	3' - 0"	7' - 0"	A	PTD HM	19/A503	19/A503	COORDINATE FRAME WITH TILE INSTALLATION
123	A1	STD	3' - 0"	7' - 0"	A	PTD HM			
124	F1	STD	6' - 3"	7' - 0"					BASIS OF DESIGN PEMKO H1100A-SW/12, SIDE WALL MOUNTED. 72" WD DOOR, SURFACE MOUNTED TO FACE OF PARTITION
125	F1	STD	6' - 3"	7' - 0"					BASIS OF DESIGN PEMKO H1100A-SW/12, SIDE WALL MOUNTED. 72" WD DOOR, SURFACE MOUNTED TO FACE OF PARTITION

TOILET ACCESSORY SCHEDULE

TAG	ITEM	SPECIFICATION	SIZE W	SIZE H	SIZE D	LOCATION	REMARKS
TA-01	MIRROR	BOBRICK B-290 1836, WELDED FRAME, STAIN FINISH	1' - 6"	3' - 0"	0' - 0 3/4"	RESTROOMS	
TA-02	BOBRICK B-2888 CLASSIC SERIES SURFACE MOUNTED MULTI-ROLL TOILET TISSUE DISPENSER	BOBRICK WASHROOM EQUIPMENT, INC.				RESTROOMS	COORDINATE WITH PLANS & ELEVATIONS
TA-03	RECESSED AUTOMATIC PAPER TOWEL DISPENSER AND WASTE RECEPTACLE	B-3961	1' - 5"	4' - 8"	0' - 9"	RESTROOMS	<varies>
TA-04	SURFACE MOUNTED AUTOMATIC FOAM SOAP DISPENSER	BOBRICK B-2013, SATIN FINISH				RESTROOMS	<varies>
TA-05	1 1/4" DIA STAINLESS STEEL GRAB BARS (36",42", 18")	BOBRICK B686				RESTROOMS	

AGCS STATE ROAD ADMINISTRATION

110 E State Rd, West Grove, PA 19390

HSA PROJECT # :26-004

Heckendorn Shiles Architects

PROJECT TEAM

CLIENT
Avon Grove Charter School
110 E State Rd
West Grove, PA 19390
484-667-5000

ARCHITECTURAL
Heckendorn Shiles Architects
347 East Conestoga Road
Wayne, PA 19087
610-994-3500

STRUCTURAL
Orndorf & Associates, Inc
8600 West Chester Pike, Suite 201
Upper Darby, PA 19802

MEPFP
Schiller & Hersh Associates, Inc.
636 Skippack Pike, Suite 200
Blue Bell, PA 19422
215-886-8947

NOT FOR CONSTRUCTION

ISSUE HISTORY

Δ	DATE	ISSUED FOR
1	11-09-2026	BID ISSUE

SHEET TITLE
SCHEDULES

DRAWING NUMBER
A601

11/10/2026 4:00:04 PM HECKENDORN SHILES ARCHITECTS expressly reserves its common law copyright and other property rights in these plans. These are not to be reproduced, nor are they to be assigned to any third party, without first obtaining the expressed written consent of HECKENDORN SHILES ARCHITECTS